



“वृक्षवल्ली आम्हा सोयरे वनचरे”



सत्यमेव जयते

महाराष्ट्र शासन

## उप वनसंरक्षक, अलिबाग यांचे कार्यालय, अलिबाग

मु.पो.हिराकोट तलावाजवळ अलिबाग ता.अलिबाग जि.रायगड पी.नं. ४०२ २०१  
दूरध्वनी क्र ०२१४१-२२२०१६/२२२२१६ Email ID:dycfalibag@mahaforest.gov.in

जावक क्रमांक: ब/२०/जमिन/वसं/२८६२/२०२५-२६.

दिनांक: १०/०९/२०२५.

प्रति,

मुख्य प्रबंधक (निर्माण),  
गेल (इंडिया) लिमिटेड, सीबीडी बेलापुर,  
नवी मुंबई

विषय:- वन जमिन रायगड.

Re-diversion of 1.7830 ha. Forest land under section 2 of the Van (Sanrakshan Evam Samvardhan) Adhiniyam, 1980 for old Uran-Usar propane pipeline laying 12" dia Liquid Propane along with OFC in Tai. Alibag, Dist. Raigad in the State of Maharashtra - regarding.

- संदर्भ:- १) केंद्रशासनाचे पत्र क्र. एफ नं. एफसी-III/एमएच-३९१/२०२४-एनजीपी/१३५१६,  
दिनांक ०५.०९.२०२४
- २) केंद्रशासनाचे पत्र क्र. एफ नं. एफसी-III/एमएच-३९१/२०२४-एनजीपी/१३९२०  
दिनांक १६.०९.२०२५
- ३) प्रकल्प यंत्रणेचे पत्र क्रमांक GAIL/UUPL/Alibag/RD/२०२५/०१  
दिनांक ०३.०२.२०२५
- ४) या कार्यालयाचे पत्र क्र. अ/२०/जमीन/वसं/२३२४, दिनांक १७.०२.२०२५
- ५) शासन पत्र क्र. एफएलडी-१३२४/प्र.क्र.८८/फ-१०, दिनांक ०४.०६.२०२५
- ६) या कार्यालयाचे पत्र क्रमांक ब/२०/जमीन/वसं/१४५६, दिनांक २४.०६.२०२५
- ७) वन परिक्षेत्र अधिकारी, अलिबाग यांचे पत्र क्रमांक अ/२०/जमीन/४७२,  
दिनांक ०९.०९.२०२५

केंद्र शासनाचे संदर्भिय पत्र क्रमांक २ अन्वये वन (संवर्धन) अधिनियम, १९८० अंतर्गत विषयांकित वनजमिन मागणीचा अट क्रमांक १ ते १६ चे अधिन राहून अंतिम मान्यता प्रदान करण्यात आली आहे. सदर अंतिम मंजूरी पत्रातील अटी/शर्तीनुसार प्रकल्प यंत्रणेकडील संदर्भिय पत्र क्र. ३

अन्वये पूर्तता अहवाल सादर केला आहे. त्याअनुषंगाने या कार्यालयाचे संदर्भित पत्र क्र. ४ अन्वये केंद्र शासनाचे अंतिम मंजूरी पत्रांतील अटी शर्तीनिहाय पुर्तता अहवाल आवश्यकत्या दस्तऐवजासह वरिष्ठांस सादर करणेत आलेले आहे. तदनंतर शासन संदर्भित पत्र क्रमांक ५ अन्वये अंतिम मंजूरी पत्राची अटी/शर्तीचा पुर्तता अहवालाच्या अनुषंगाने अट क्रमांक २ व ५ बाबत मुददे उपस्थित केलेले आहेत.

त्याअनुषंगाने केंद्रशासनाचे अंतिम मंजूरी पत्रातील अट क्रमांक २ चे अनुषंगाने या कार्यालयाचे संदर्भित पत्र क्रमांक ६ मधील सुचनानुसार, वन परिक्षेत्र अधिकारी, अलिबाग यांचेकडील संदर्भिय पत्र क्रमांक ७ अन्वये सदर प्रस्तावात बाधीत होणारे वनक्षेत्राचे सिमांकनाचे Boundry Demarcation Pillars चे रक्कम रु. १६,५४,५१३/- (सोळा लक्ष चौपन्न हजार पाचशे तेरा मात्र) चे अंदाजपत्रक या कार्यालयाकडे सादर केले आहे.

त्याअनुषंगाने कळविणेत येते की, सदर प्रस्तावात बाधीत होणारे वनक्षेत्राचे सिमांकनाचे (Boundary Demarcation Pillars) आवश्यक १६,५४,५१३/- (सोळा लक्ष चौपन्न हजार पाचशे तेरा मात्र) या अंदाजपत्रकीय रक्कम कॅम्पाकडे भरणा करून, अंतिम मंजूरी पत्रातील अट क्रमांक २ व ५ चे अनुषंगाने आवश्यक दस्तऐवजासह ५ प्रतीत अहवाल या कार्यालयास सादर करावा.

  
(राहुल पाटील, भा.व.से.)

उप वनसंरक्षक,  
अलिबाग वन विभाग, अलिबाग.

सहपत्र:- वरील प्रमाणे.

प्रतिलिपी:- अपर प्रधान मुख्य वनसंरक्षक व केंद्रस्थ अधिकारी, महाराष्ट्र राज्य, नागपूर यांचेकडे माहितीसाठी सादर.

प्रतिलिपी:- मुख्य वनसंरक्षक, ठाणे यांचेकडे माहितीसाठी सादर.

प्रत:- सहा. वनसंरक्षक, अलिबाग व वन परिक्षेत्र अधिकारी, अलिबाग यांना माहिती व जरूरत्या कार्यवाहीसाठी रवाना.

# **Demarcation Estimate**

**Range: Alibag**

**Division: Alibag**

**Estimate – INR 16,54,513.00**

**DETAIL ESTIMATE**

**FOREST DEPARTMENT**



**Division - Alibag  
Alibag - Range**

**Erection of Boundary Demarcation Pillars**

Class I	75 Nos
Class II	68 Nos

**Name of Work:- Boundary Demarcation Pillars at Uran - Usar Pipeline,**

**Village Talashet, Dalvi Kharoshi, Bopoli, Beloshi, Kune, Tal. Alibag.**

**Work Portion Amount Rs. = 16,54,513/-**

**FACE SHEET**

Division **Alibag**  
Sanction Estimate :-  
Fund Head :-  
Major Head :-  
Minor Head :-  
Service Head :-  
Departmental Head :-

**Estimate framed in the office of the Range Forest Office, Alibag Range and the probable expenses that will incurred in the Erection of boundary demarcation pillar**

**Village of Talashet, Dalvi Kharoshi, Bopoli, Beloshi, Kune, Taluka Alibag**

**Total Amount Rs. = 16,54,513/-**

Administrative approved under No. Dated

Technically sanctioned under No. Dated

Estimate prepared by Shri

Estimate Checked by Shri

Call of Authority **D.F.O., Alibag**

General Description as per separate sheet attached

  
**Range Forest Officer  
Alibag**

  
**(Rahul Patil, IFS)  
Deputy Conservator of Forest,  
Alibag Forest Division, Alibag**

## ESTIMATE

Division :- Alibag Forest Division  
Range :- Alibag Forest Range

**Name of Work:** -

For Re-Diversion of 1.7830 Ha forest land for laying 12" Dia Liquid Propane Pipeline along with OFC from Uran to Usar across Reserved / Revenue Forest in Right of Way/Use of alibag forest division in Raigad District for Re-Diversion forest proposals falling under your Jurisdiction

Class-I Pillars 75 Nos  
Class-II Pillars 68 Nos

Rs. = 16,54,513/-

### GENERAL DESCRIPTION

SI No	Details :	Length	Area in Ha
1	Village - Talashet, Survey No - 42 (34)	155.36	0.0777
2	Village - Talashet, Survey No - 42 (34)	41.99	0.021
3	Village - Talashet, Survey No - 64 (51)	37.36	0.0187
4	Village - Talashet, Survey No - 68 (58)	23.12	0.0116
5	Village - Dalvi Kharoshi, Survey No - 13	16.13	0.0081
6	Village - Bopoli, Survey No - 23	138.96	0.0695
7	Village - Bopoli, Survey No - 22	163.42	0.0817
8	Village - Bopoli, Survey No - 22	170.02	0.085
9	Village - Bopoli, Survey No - 17	330.91	0.1655
10	Village - Bopoli, Survey No - 37	111.76	0.0559
11	Village - Dalvi Kharoshi, Survey No - 13	552.48	0.2762
12	Village - Beloshi, Survey No - 90, 110, 168	1050.53	0.5253
13	Village - Kune, Survey No - 98	654.34	0.3272
14	Village - Kune, Survey No - 152 (49/3)	29.72	0.0149
15	Village - Kune, Survey No - 158 (52)	89.44	0.0447
<b>Total</b>		<b>3565.54</b>	<b>1.783</b>

**Name of Work: -**

For Re-Diversion of 1.7830 Ha forest land for laying 12" Dia Liquid Propane Pipeline along with OFC from Uran to Usar across Reserved / Revenue Forest in Right of Way/Use of alibag forest division in Raigad District for Re-Diversion forest proposals falling under your Jurisdiction

**RECAPITULATION SHEET**

SI No	Description	Amount (in Rs)
1	Estimated Civil Cost	<b>13,10,856.41</b>
2	Add G.S.T. @ 18 %	2,35,954.00
3	Add Contingencies @ 4 %	52,434.00
4	Add for Labour Insurance @ 1 %	13,109.00
5	Add for Estimate Charges	29,494.00
6	Add for Royalty Charges	5,251.03
7	Add for Material Checking charges	7,415.00
	<b>Total Amount</b>	<b>16,54,513.00</b>

**Name of Work: -**

For Re-Diversion of 1.7830 Ha forest land for laying 12" Dia Liquid Propane Pipeline along with OFC from Uran to Usar across Reserved / Revenue Forest in Right of Way/Use of alibag forest division in Raigad District for Re-Diversion forest proposals falling under your Jurisdiction

**Forest Division - Alibag Forest Division**

**Forest Range - Alibag**

**ABSTRACT**

Qty	Item of Work	Rate	Unit	Amount
28600.00	<b>Item No. 1:-</b> Removing Grass, Gazer Grass and disposing off out of building premises including making clean the ground by shovel and phavaras etc. complete.	6.60	Sqmt	1,88,760.00
40.2810	<b>Item No. 2:-</b> Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	227.70	Cum	9,171.98
20.14	<b>Item No. 3 :-</b> Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	2211.79	Cum	44,546.56
76.97	<b>Item No. 4:-</b> Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	8425.92	Cum	6,48,516.94
483.21	<b>Item No. 5:-</b> Providing internal cement plaster 6 mm thick in a single coat in cement mortar 1:3 without neeru finish to concrete surface in all positions including scaffolding and curing etc. complete.	233.61	Sqmt	1,12,882.69
37.82	<b>Item No. 6:-</b> Providing and applying two coats of flat oil paint of approved colour and shade to internal / external plastered surfaces including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	111.10	Sqmt	4,202.19
4576.00	<b>Item No. 7:-</b> Painting letters upto 20 cm height complete brushes, coir brushers, dusting, cleaning, including cost of paint etc. complete.	31.90	Nos	1,45,974.40
483.21	<b>Item No. 8:-</b> Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface, applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete.	324.50	Sqmt	1,56,801.65
<b>Total</b>				<b>13,10,856.41</b>

	Item No. 9:- Royalty Charges. @ 0			--
3.67	1. Sand	237.37	Cum	871.72
20.26	2. Rubble	216.18	Cum	4,379.31
		Total		<b>5,251.03</b>
	<b>Item No. 10:-</b> Material Checking charges.			7,415.00

**Name of Work: -**

For Re-Diversion of 1.7830 Ha forest land for laying 12" Dia Liquid Propane Pipeline along with OFC from Uran to Usar across Reserved / Revenue Forest in Right of Way/Use of alibag forest division in Raigad District for Re-Diversion forest proposals falling under your Jurisdiction

**Forest Division - Alibag Forest Division**  
**Forest Rang - Alibag**

**MEASUREMENT SHEET**

**Class-I Pillars      75**  
**Class-II Pillars     68**

**Item No 1:** - Removing grass, gazer grass and disposing off out of building premises including making clean the ground by shovel and phavaras etc. complete.

Class-I Pillars =  $75 \times 100.00 \times 2.00 = 15,000.00$  Sqmt

Class-II Pillars =  $68 \times 100.00 \times 2.00 = 13,600.00$  Sqmt

**Total = 28,600.00 Sqmt**

**Item No. 2:** - Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed...

Class-I Pillars =  $75 \times 1.10 \times 1.10 \times 0.30 = 27.23$  Cum

Class-II Pillars =  $68 \times 0.80 \times 0.80 \times 0.30 = 13.06$  Cum

**Total = 40.28 Cum**

**Item No. 3:** - Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete..

Class-I Pillars =  $75 \times 1.10 \times 1.10 \times 0.15 = 13.61$  Cum

Class-II Pillars =  $68 \times 0.80 \times 0.80 \times 0.15 = 6.53$  Cum

**Total = 20.14 Cum**

**Item No. 4:** - Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap / granite / quartzite / gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying / pumping, compacting.....

Volume of one Class-I Pillar (Ref. Drawing) = 0.741Cum

Volume of one Class-II Pillar (Ref. Drawing) = 0.289 Cum

Class-I Pillars =  $75 \times 0.741 = 55.58$  Cum

Class-I Pedestal at top =  $75 \times 0.23 \times 0.23 \times 0.23 = 0.91$  Cum

Class-II Pillars =  $68 \times 0.289 = 19.65$  Cum

Class-II Pedestal at top =  $68 \times 0.23 \times 0.23 \times 0.23 = 0.83$  Cum

**Total = 76.97 Cum**

**Name of Work:** -

For Re-Diversion of 1.7830 Ha forest land for laying 12" Dia Liquid Propane Pipeline along with OFC from Uran to Usar across Reserved / Revenue Forest in Right of Way/Use of alibag forest division in Raigad District for Re-Diversion forest proposals falling under your Jurisdiction

**Forest Division - Alibag Forest Division**  
**Forest Rang - Alibag**

**MEASUREMENT SHEET**

**Item No. 5:** - Providing internal cement plaster 6 mm thick in a single coat in cement mortar 1:3 without neeru finish to concrete surface in all positions including scaffolding and curing etc.....

$$\text{Class-I Pillars} = 75 \times 4.00 \times (0.90 + 0.60)/2 \times 1.30 = 292.50 \text{ Sqmt}$$

$$\text{Class-I Side Top \& Pedestal Top} = 75 \times 0.60 \times 0.60 = 27.00 \text{ Sqmt}$$

$$\text{Class-II Pillars} = 68 \times 4.00 \times (0.60 + 0.45)/2 \times 1.05 = 149.94 \text{ Sqmt}$$

$$\text{Class-II Side Top \& Pedestal Top} = 68 \times 0.45 \times 0.45 = 13.77 \text{ Sqmt}$$

$$\text{Total} = 483.21 \text{ Sqmt}$$

**Item No. 6:** - Providing and applying two coats of flat oil paint of approved colour and shade to internal / external plastered surfaces including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc....

$$\text{Class-I Pillars Sides} = 75 \times 4.00 \times (0.83 + 0.60)/2 \times 0.23 = 15.87 \text{ Sqmt}$$

$$\text{Class-I Pillars Pedestal block sides} = 75 \times 1 \times 0.23 \times 0.23 = 3.97 \text{ Sqmt}$$

$$\text{Class-II Pillars Sides} = 68 \times 4.00 \times (0.60 + 0.45)/2 \times 0.23 = 14.39 \text{ Sqmt}$$

$$\text{Class-II Pillars Pedestal block sides} = 68 \times 1 \times 0.23 \times 0.23 = 3.60 \text{ Sqmt}$$

$$\text{Total} = 37.82 \text{ Sqmt}$$

**Item No. 7:** - Painting letters upto 20 cm height complete brushes, coir brushers, dusting, cleaning, including cost of paint etc. complete.....

$$\text{Class-I Pillars} = 75 \times 4 \times 8 = 2,400 \text{ Nos}$$

$$\text{Class-II Pillars} = 68 \times 4 \times 8 = 2,176 \text{ Nos}$$

$$\text{Total} = 4,576.00 \text{ Nos}$$

**Item No. 8:** - Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface, applying primer coat..

$$\text{Qty. same as Item No. 5} = 483.21 \text{ Sqmt}$$

**Name of Work: -**

For Re-Diversion of 1.7830 Ha forest land for laying 12" Dia Liquid Propane Pipeline along with OFC from Uran to Usar across Reserved / Revenue Forest in Right of Way/Use of alibag forest division in Raigad District for Re-Diversion forest proposals falling under your Jurisdiction

**Forest Division - Alibag Forest Division**  
**Forest Rang - Alibag**

**MEASUREMENT SHEET**

**Item No. 9: - Royalty charges.**


1. Rubble -  $76.97 \times 0.2632 = 20.258$  Cum
  2. Sand in Plaster -  $483.21 \times 0.0076 = 3.67$  Cum
- Total = 23.93 Cum

**Item No. 10: - Material checking charges.. @7415**




# Construction of Class - I Permanent Boundary Pillars for Forest Area

## Class - I




**SECTIONAL ELEVATION**



**ISOMETRIC ELEVATION**

DATAS:


A1 (Top Area)	=	$0.60 \times 0.60$	=	0.36	Sqrm
A2 (Bottom Area)	=	$0.90 \times 0.90$	=	0.81	Sqrm
H Total Height	=	1.30 M			
H1 Below GL	=	0.30 M			
H2 Above GL	=	1.00 M			
Volume	=	$H/3 \times (A1 + A2 + \sqrt{A1A2})$			
	=	$1.30/3 \times (0.36 + 0.81 + \sqrt{0.36 \times 0.81})$			
	=	0.741		Cum	




**PLAN**

# Construction of Class - II Permanent Boundary Pillars for Forest Area

## Class - II




SECTIONAL ELEVATION



ISOMETRIC ELEVATION

DATAS:

A1 (Top Area)	=	0.45X0.45	=	0.20	Sq.m
A2 (Bottom Area)	=	0.60X0.60	=	0.36	Sq.m
H Total Height	=	1.05 M			
H1 Below GL	=	0.30 M			
H2 Above GL	=	0.75 M			
Volume	=	H/3X (A1+A2+√A1A2)			
	=	1.05/3X(0.20+0.36+√0.20X0.36)			
	=	0.289	Cum		



PLAN