

BADNAWAR MICRO LIFT IRRIGATION SCHEME

ALTERNATIVE ROUTE EXAMINATION IN FOREST AREA

	TOTAL LENGTH MTR	LENGTH IN FOREST MTR	
ALTERNATIVE 1	23704	13597	SELECTED
ALTERNATIVE 2	24311	17077	
ALTERNATIVE 3	26216	14880	

Alternative-1 is found to be **moresuitable** option because of the following reasons

- In alternatives 2 & 3 the forest length is more than the alternative 1.
- In alternative 2 & 3 total length of the rising main is much more than the alternative-1 adding up to extra cost.
- In alternatives 2 & 3 at many places the permanent structures are coming very near to the alignment and it is very difficult to avoid them without further increasing the length of the rising main.
- And in alternative 2 & 3 there are many hillocks as it is crossing forest at many places and it is very difficult to route the pipeline.



Executive Engineer,
OSP Canal Division
Dhamnod Distt. Dhar

BADNAWAR MICRO LIFT IRRIGATION PROJECT (PIPE LINE)
DISTRICT DHAR, ALTERNATIVE MAP

