

कार्यालय क्षेत्रीय प्रमुख
खनिज साधन विभाग, मध्यप्रदेश शासन
संचालनालय भौमिकी तथा खनिकर्म
क्षेत्रीय कार्यालय रीवा, मध्यप्रदेश
ई-मेल — rhdgmrew@mp.gov.in

क्रमांक

/मा.प्ला./न.क्र./2021

रीवा, दिनांक

प्रति,

स्वामी नित्यानंद जी महाराज स्टोन्स
प्रो. श्री ललित पंधाल
निवासी मकान नंबर 975/76 सेक्टर 13,
हुड़डा भिवानी, हरियाणा

विषय :— खनन योजना के अनुमोदन बाबत।

संदर्भ :— 1. कार्यालय कलेक्टर (खनिज शाखा) जिला रीवा का आदेश क्रमांक 5939/खनिज/2021 रीवा, दिनांक 11.10.2021
2. इस कार्यालय का आवक क्रमांक 1308 दिनांक 23.12.2021

—00—

उपरोक्त विषयांतर्गत संदर्भित पत्र के माध्यम से ग्राम सरदगम, तहसील हनुमना, जिला रीवा (म.प्र.) के खसारा क्रमांक 677/2क पी. (वन भूमि) रक्कवा 2,800 हेक्टेक्टर पर खनिज पत्थर (थोन्ट्रिकी क्रिया से गिरी निर्माण) उत्खनिपट्टा की खनन योजना आरक्ष्य पी. श्री पुष्पेन्द्र कुमार तिवारी द्वारा मध्यप्रदेश गौण खनिज नियम, 1996 के नियम-42 के अंतर्गत अनुमोदन हेतु प्रस्तुत की गई है।

प्रस्तुत खनन योजना मध्यप्रदेश गौण खनिज नियम, 1996 के नियम 42 (सी) के अधीन प्रदत्त अधिकारों के अंतर्गत अवधि अनुबंध निष्पादन दिनांक से 05 वर्ष (2022-2023 से 2026-2027) तक के लिये अनुमोदित बी जाती है।

यह खनन योजना अनुमोदन निम्नलिखित शर्तों के अधीन होगा :—

1. आवेदक को वन संरक्षण अधिनियम 1980 के तहत व्यपवर्तन की कार्यवाही करनी होगी।
2. खनन योजना का अनुमोदन केन्द्र सरकार, राज्य सरकार अथवा अन्य किसी प्राधिकारी द्वारा रामय-समय पर लागू किये गये कानूनों पर किसी प्रकार का प्रतिकूल प्रभाव डाले बिना किया गया है।
3. इस खनन योजना का अनुमोदन किसी भी न्यायालय के सकार क्षेत्राधिकार के किसी अन्य आदेश या निर्देश पर प्रभाव डाले बिना किया गया है।
4. खान अधिनियम 1952 और उसके अधीन बनाये गये नियमों/उपबंधों का पट्टेदार द्वारा पालन किया जावेगा।
5. किसी भी स्तर पर यदि यह देखा गया कि खनन योजना में दी गई जानकारी गलत या गलत तरीके से लायी गयी है, तो इस खनन योजना का अनुमोदन तत्काल प्रभाव से रद्द कर दिया जावेगा।
6. म.प्र. राज्य सरकार के आदेश दिनांक 10.08.2011 अनुसार अनुमोदित खनन योजना में यदि प्रस्तावित उत्पादन में वृद्धि होती है तो ऐसी परिस्थितियों में उत्पादन की बढ़ी हुई

मात्रा के लिये पट्टेदार द्वारा अतिरिक्त स्टाम्प शुल्क का भुगतान किया जायेगा एवं पट्टेदार द्वारा एक पूरक अनुबंध निष्पादित किया जायेगा।

7. पट्टेदार को निर्देशित किया जाता है कि एक साल की अवधि के अंदर स्वीकृति क्षेत्र का डी.जी.पी.एस. सर्वे करायें।
8. उपरोक्तानुसार शताँ के अलावा आवेदक/पट्टेदार द्वारा म.प्र. गौण खनिज नियम 1996 के समस्त प्रावधानों का पालन करना अनिवार्य होगा।
9. यदि यह अनुमोदन किसी अन्य कानून या अदालत के आदेश/निर्देश से प्रतिकूल होता है तो यह अनुमोदन तत्काल प्रभाव से स्वतः निरस्त माना जावेगा।
10. इस खनन योजना के अवधि समाप्त होने के 120 दिवस पूर्व खनन स्कीम प्रस्तुत की जावे, यदि इस अवधि में स्कीम प्रस्तुत नहीं की जाती है तब म.प्र. गौण खनिज नियम 1996 के नियम 30(27) के तहत दण्डनीय होगा।

संलग्न :— खनन योजना एक प्रति।

क्षेत्रीय प्रमुख
क्षेत्रीय प्रमुख
संचालनालय भौमिकी तथा खनिजम
क्षेत्रीय कार्यालय रीवा, (मध्य)प्रदेश
रीवा, दिनांक २५/०१/२०२२

पृ. क्रमांक १०२ /मा.प्ला./न.क्र./2021

प्रतिलिपि :—
✓ कलेक्टर, (खनिज शाखा) जिला रीवा (म.प्र.) की ओर खनन योजना की एक प्रति संलग्न कर आवश्यक कार्यवाही हेतु प्रेषित।

क्षेत्रीय प्रमुख
संचालनालय भौमिकी तथा खनिजम
क्षेत्रीय कार्यालय रीवा, (मध्य)प्रदेश

डाक पावती

खनिज अधिकारी, रीवा

विषय—

कार्यालय क्षेत्रीय प्रमुख खनिज संसाधन विभाग, संचालनालय, भौमिकी तथा खनिकर्म क्षेत्रीय कार्यालय रीवा से स्वीकृत माईनिंग प्लानस की एक—एक प्रति जमा करने बावत ।

—00—

उपरोक्त विषय के अंतर्गत निम्नानुसार तीन स्वीकृत माईनिंग प्लानस की एक—एक प्रति स्वीकृत पत्रों के साथ आपके कार्यालय में जमा करवाई जा रही है—

1—ग्राम हराई गुजरान, तहसील—मऊगंज, जिला —रीवा । खसरा नम्बर —2/1 (p) क्षेत्रफल —4.590 है. (शासकीय वन भूमि) । वन कक्ष क्रमांक—पी—334, बीट—काडुवान, परिक्षेत्र मऊगंज, रीवा वनमण्डल ।

2—ग्राम—हराई गुजरान , तहसील—मऊगंज, जिला —रीवा । खसरा नम्बर —2/1 (p) क्षेत्रफल —4.460 है. (शासकीय वन भूमि) । वन कक्ष क्रमांक—पी—334, बीट—काडुवान, परिक्षेत्र—मऊगंज, रीवा वनमण्डल ।

3—ग्राम सारदामान , तहसील—हनुमना, जिला —रीवा । खसरा नम्बर—677/2 KA(p) क्षेत्रफल — 2 .800 है. (शासकीय वन भूमि) । वन कक्ष क्रमांक—पी—339, बीट—सारदामान परिक्षेत्र—हनुमना, रीवा वनमण्डल ।

हस्ताक्षर एवं दिनांक

डाक प्राप्तकर्ता

1308
Date.... 23/12/2021

MINING PLAN & PROGRESSIVE MINE CLOSURE PLAN

FOR SARDAMAN STONE QUARRY LEASE

(FOR MAKING GITTI THROUGH STONE CRUSHER)

अधिक जगहाएँ पर कृषक-
किस जानी यथा में अप. गोप जिल्हा नियम १२३-
के तियाम ३० (२४) प्रारंभ होता है तथा अन्यायित नियम
DGMMS धरकार, IBM वालाएँ उन्हें अधिकारी को लिखाएँ-
के करोड़ एवं रुपयोग अधिकारी को लिखाएँ-
तकाल रुपयोग किया जाता अधिकारी के

VILLAGE – SARDAMAN, TEHSIL – HANUMANA

DISTRICT - REWA (M.P.)

KHASARA NO. 677/2KA (P) AREA: 2.800 Ha. (Govt. Forest Land)

(Forest Comp. No. : P-399 Beat – Sardaman, Range – Hanumana, Rewa Division)

LEASE PERIOD : 10 YEAR (From date of Agreement)

(PERIOD OF MINING PLAN 05 YEAR)

Prepared Under Rule Sub- Section 42(C) of Madhya Pradesh
Miner Mineral Rule 1996, Amendment Rule, 2013

December, 2021



P.K. Tiwari
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

APPLICANT

SWAMI NITYANANDJI MAHARAJ STONES
PROP. SHRI LALIT PANGHAL

R/W House no. 975/76, Sector 13, Hudda Bhiwani
District Bhiwani, Haryana

PREPARED BY

PUSHPENDRA KUMAR TIWARI
Reg: RQP/DGMMP/30/2013
Mob. : 9424933558



MINING PLAN FOR SARDAMAN (QUARRY LEASE)

MP ID : 34518
MP SUBMISSION DATE : 07/12/2021
SUBMITTED AT : Rewa
VILLAGE : SARADHAMAN 958
DISTRICT : REWA
TEHSIL : HANUMANA
MINERAL : Gitti
KHASRA NO : 677/2 KA
AREA : 2.8000 HECTARE

PROPOSED PRODUCTION:

PROPOSED MINERAL PRODUCTION DETAILS..

YEAR	FIN. YEAR	PROD. QTY.	UNIT
YEAR-1	2022-2023	39900	CUBIC METER
YEAR-2	2023-2024	39900	CUBIC METER
YEAR-3	2024-2025	39900	CUBIC METER
YEAR-4	2025-2026	39900	CUBIC METER
YEAR-5	2026-2027	39900	CUBIC METER
TOTAL PRODUCTION		199500	CUBIC METER

STATE : M.P
LEASE PERIOD : 10 Year
SANCTION ORDER NO. : 5939/KHANJIJ/2021, REWA
SANCTION ORDER DATE : 11/10/2021

SUBMITTED UNDER RULES 42 OF MPMMR,1996 FOR APPROVAL OF QUARRY LEASE

LESSEE:


NAME: SWAMI NITYANANDJI MAHARAJ STONES
FATHER NAME: PROP. SHRI LALIT PANGHAL
ADDRESS: HOUSE NO. 975/76 SECTOR 13, HUDDA BHIWANI, DISTRICT BHIWANI, HARYANA
DISTRICT: REWA

PREPARED BY:

RQP NAME : PUSHPENDRA TIWARI
RQP ADDRESS : GRAM & POST LOHI, TEHSIL HUJUR, DISTRICT REWA, MP
RQP REGISTRATION : RQP/DGMMP/30/2013
VALID UP TO : 09/05/2023
MOBILE NO : 9424933558

CONTENT'S

Chapters	Description	Page No.
1	General	1-2
2	Location and Accessibility	3-5
3	Geology and Reserves	6-12
4	Mining	13-18
5	Mine Drainage	19
6	Stacking of mineral reject and disposal of waste	20
7	Provision for separate stacking of surface soil excavated from mining operation and its utility	21-22
8	Use of mineral	23
9	Others	24
10	Mineral processing/beneficiation	25
11	Any other matter which is directed to include in mining plan	26
12	Environment management plan	27-34
13	Progressive mine closure plan	35-43
	Consent from the applicant	44
	Undertaking	45


 P.K. Tripathi
 Environment Minister
 10.01.2019

LIST OF ANNEXURE

Annexure	Description
I	Reference No. and Consent letter from State Govt.
II	Copy of Revenue Map
III	Copy of Khasra
IV	RQP Certificate

LIST OF PLATE (MAP)

S.No.	Description
1	Map showing QL Area in DRM of Rewa District
2	Location Map
3	Geological Plan and Section
4	Conceptual Plan and Section
5	Five year working
6	Land use map
7	Environmental Management Plan
8	Progressive Mine Closer Plan

P. K. T.
Bhagwanji Ramu Tiwari
RQP/PLATE/170/2010

CHAPTER -1

1.0 GENERAL

i	Name of Applicant	Swami Nityanandji Maharaj Stones
ii	Address	Prop. Shri Lalit Panghal, R/o House no. 975/76, Sector 13, Hudda, Bhiwani, District Bhiwani, Haryana
iii	Phone	8307520901
iv	Status of Applicant	Proprietorship Firm
v	Mineral(s), which occurring in the area and which the applicant intends to mine	Sand stone (quartzitic nature) for making gitti
vi	Proposed Quarry Lease Period	10 Year (from agreement)
vii	Mining Plan Period	5 Year
viii	Category of Mine	B

1.1 NAME OF RQP PREPARING MINING PLAN

i	Name	Pushpendra Kumar Tiwari
ii	Address	Village & Post Lohi, Tehsil HUzur District Rewa (M.P.)
iii	Phone	09424933558
v	E.mail	geopushpendra@rediffmail.com
vi	Registration No.	RQP/DGMMP/30/2013

Regional Head
D'rate of Geolgy & Mining
Regional Office, Rewa (M.P.)

1.2 NAME OF PROSPECTING AGENCY :- N.A.

1.3 REFERENCE NO. AND DATE OF CONCENT LETTER FROM THE STATE GOVERNMENT:-

The quarry lease area is a protected Forest and thus attracts the Provisions of Forest Conservation Act, 1980. After approval of mining plan, Applicant should be applying for diversion of forest land under FCA Act 1980. The Collector (Mining branch) Rewa, sanctioned in principal quarry lease vide its letter No 5939/khanij/2021,

Rewa dated 11.10.2021 (**Annexure I**), addressed to Swami Nityanandji Maharaj Stones.

1.4 STATUS OF STATUTORY CLEARANCE

S.No.	Statutory Clearance	Present Status
1	Forest Clearance	To be obtained
2	Environment Clearance	EC will be obtained from MoEF and CC
3	Surface Rights	Total area of 2.800 Ha. is forest land and surface rights will be obtained from forest department after forest clearance from MoEF and CC

The area under quarry lease is forest land and forest clearance will be obtained from MoEF &CC. The conditions imposed by the MoEF &CC and the same will be implemented during the span of mining plan period.

3
Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)

P.K.T.
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

CHAPTER -2

2.0 LOCATION AND ACCESSIBILITY:

2.1.1 BY ROAD:-Area is located at East direction of Rewa city (District H.Q.) 85 km and about 20 km SW of Hanumana tehsil. The accessibility of the area is by well Metal road connected from Rewa to Sardaman via Mauganj. The approachability is by means of regular Bus/Private Taxis which is easily available up to Sardaman.

2.1.2 BY TRAIN

The applied area can't be accessed; nearly station is Rewa is about 85 km from the applied area.

2.2 Name and distances of major town and utility

The details of major town and other details are given below:

TOWN	DISTANCE	DIRECTION	UTILITY
Rewa	85 KM	West	District Head Quarter of Rewa District. In this place all facilities like Education, Transportation, and Hospitals etc. are available

2.3 Climate:

The area witnesses the subtropical climate with a averaging rainfall of 900-1000 mm annually. The variation in temperature is 40° to 46° c during summer and winter 2°C respectively. The wind generally blows in northeast direction. From November to February the area experiences pleasant winter. March is start of summer, which continues up to June. The monsoon sets in by June and retreats by September. Relative humidity varies to averages between 20% to 75%.

Propose prospecting operations are of small scale and will not cause adverse effect on environment of the area. Standard norms will be adopted for protection of environment.

Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013


2.4 Physiography

The area under quarry lease is of 2.800 Ha is new quarry lease case which is granted by the State Govt. Topographically point of view it's a almost undulating topography. The quarry lease has highest elevation of 333 m & lowest one is 329 MRL , thus total elevation difference is of 4 m and slope towards north of the area. Overall drainage is towards north parts of the area.

2.5 Local Resources

2.5.1 WATER

Source of drinking water is available inside the stone crusher plant.


2.5.2 ELECTRICITY: Electricity facility is available in the Applied area .Nearest electricity facility is available at Sardaman Village.

2.5.3 MANPOWER

Man power is easily available from the surrounding villages i.e Sardaman, Harraipratap Singh, Damodargarh etc.

2.5.4 OTHER FACILITIES: Nearest hotels and Restaurants is available in at Hanuman which is NE direction from the area.

2.5.5 INFRASTRUCTURES

Presently no infrastructures have developed in the applied area. The daily needs facilities are available in Sardaman Villages while the other requirements are easily from Rewa.

2.6 DETAILS OF THE AREA

Details of khasra no. and area are given as follows (Annexure 2)

*Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.R.)*


i	District	Rewa
ii	Taluka	Hanumana
iii	Village	Sardaman
iv	Area	2.800 Ha
v	Khasra No.	677/2 ka
vi	Forest Comp. No.	P-399 (Beat Sardaman, Hanumana Range)
vii	Occupancy	Govt. Forest Land

*Khasra panchsala is enclosed along with khasra map.

2.6.1 WHETHER AREA IS RECORDED IN FOREST: Yes

2.6.1.2 TYPES OF LAND

Forest (specify)	Area (Ha.)	Non Forest (Specify)	Area (Ha.)	Total
Forest Comp. No. P-399 (Beat Sardaman, Range Hanumana, Rewa Division) Open Mixed Jungle	2.800	Nil	Nil	2.800 Ha.



2.6.2 EXISTENCE OF PUBLIC ROAD: No public Road is passing through the lease area.

2.6.3 TOPOSHEET NO.: Area falls in survey of India degree topo sheet No.63 L/2

2.6.4 COORDINATE OF CORNER POINT OF QUARRY LEASE (Garmin GPS Used)

There are 06 corner points and Lat./Long. values of these pillars are given in the sketch enclosed as key plan and surface plan Plate-01 and Plate-03 respectively and also listed in below Table-

Corner Point	Latitude	Longitude
A	24°35'8.360"N	82° 0'23.678"E
B	24°35'13.003"N	82° 0'27.096"E
C	24°35'15.340"N	N82° 0'32.540"E
D	24°35'15.607"N	82° 0'34.858"E
E	24°35'10.911"N	82° 0'30.039"E
F	24°35'6.519"N	82° 0'24.950"E

Source: DGPS survey report

2.6.5 LAND USE PATTERN: Govt. forest land.

2.6.6 VALIDITY OF LEASE PERIOD: The period for the lease will be 10 years from the date of execution as per MPMMR rule 1996.

*Regional Head
District of Geology & Mining
Regional Office, Rewa (M.P.)*

CHAPTER-3

3.0 GEOLOGY AND RESERVES

3.1.1 TOPOGRAPHY

The area under quarry lease is of 2.800 Ha is new quarry lease case which is granted by the State Govt. Topographically point of view it's a almost undulating topography. The quarry lease has highest elevation of 333 m & lowest one is 329 MRL , thus total elevation difference is of 4 m and slope towards north of the area. Overall drainage is towards north parts of the area.

3.1.2 REGIONAL GEOLOGY

The regional geological setup of Rewa district is characterized by the occurrence of early Paleozoic rocks and sediment of Vindhyan basin. The present area of quarry lease constitutes a part of the upper vindhyan system.

The Vindhyan system has been divided in to the lower and upper division of very unequal proportions, but just justified by an unconformity between the two parts, quite apparent at some places and nonresistant at others, and also by a sharp lithological contrast between the lower and upper portions of the system the main division of the Vindhyan are shown in following table-

CLASSIFICATION OF THE VINDHYAN SUPER GROUP

(Modified after Auden, 1933)

Table: 3.1

Super Group	Group	Formation	Thickness
V		Upper Bhander Shale (Calcareous & Siliceous) Sirbu shale	
	Bhander group	Lower Bhander Shale	1000 m.
		Bhander limestone	
I		Ganurgarh shales	

PREPARED BY: PUSHPENDRA KUMAR TIWARI, RQP /DGMMP/30/2013

6

P.K.Ti.
Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)

Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

			Upper Rewa Shale	2000 m.
			Jhiri shales	
N	Upper	Rewa group	Lower Rewa Shale	
	Vindhyan		Panna shale	
			Upper Kaimur Shale	
D		Kaimur group	Bijaigarh shale	400 m.
			Lower Kaimur Shale	
H-----	U-----	C-----O-----N-----F-----O-----R-----M-----I-----T-----Y-----		
			Rohtas formation:	1300 m.
Y			Suket shale	
			Nimbahera limestone and shale	
			Conglomerate and Shale	
			(Calcareous & Siliceous)	
	Lower		Khenjua formation:	
A	Vindhyan	Semri Group	Gluconitic member	
			Fawn limestone	
			Olive shales	
			Porcellinite Formation;	
N			Porcellinic shales	
			Trappoid beds	
			Pocellinite shales	
			Basal formation:	
			Kajarahat limestone	
			Bleaching shales	
			Basal Quartzite and	
			conglomerate	

The principal geological formations of the upper Vindhyan are Kaimur group, Rewa group and Bhander group, which are described as follows.

Kaimur group:

The Kaimur are mainly arenaceous formation with inter bedded shale with which are associated carbonaceous shales and band of Siderite (iron-

carbonate) and Pyrite matter. An assemblage of Shale (Calcareous & Siliceous), shales Shalestone and porcillinite overlying the Semri group has been designated as the Kaimur group, being the lowest unit of the upper part of the Vindhyan Supergroup. It has derived its name from the Kaimur range in central India, which divides the valley of Tons with that of the Son. The name was first suggested by (Oldham, 1856) for the lowest "series" of Vindhyan system. Thickness of the Kaimur varies enormously, from a few meter to 400 m. (Pascoe, 1968). The general succession of the Kaimur group as deduced by (Auden, 1933) is given in table- 3.1.

Rewa group:

The Rewa group comprising a 2000-meter thick succession of red shale and Sand stone beds in separated from the underlying succession of the Kaimur group by a diamond-bearing horizon of conglomerate. The conglomerate bed about 70 cm. In thickness consist of pebbles of vein quartz, jasper and green quartzite in a matrix of sand and clay. Diamond occurs as placer deposit in the form of granules and grains in the matrix. The Rewa group consists of rather coarse Shale and sandstone showing current bedding. The Rewa succession having less consistent lithological characters compared to the other two groups has been further subdivided in to alternating shale and Shale formation (table-3.1). A Diamond bearing conglomerate horizons again marks the upper limit of the Rewa group. The famous Panna diamond field of India is situated in the country of Rewa rocks. The name was originally coined by (Oldham, 1856) after Rewa district in Madhya Pradesh.

Bhander group:

As a result of the very flat basin like nature of the main Vindhyan area, the youngest series namely Bhander covers a larger exposed surface than the others, its outcrop include a very large tract from Sauger to beyond Rewa, spreading over a wide extent of country southwest of Agra. A considerable portion of the trap area north of the Narmada series is proved by the occurrence of inliers far away from the boundary of the main outcrop. The

Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

succession has been divided in to five formations. The upper Bhander sand stone having a uniformly fine-grained character, has been the most popular and versatile building stone of northern India. of the lower Bhander, the Ganurgarh shales at the bottom and the Sirbu shale at the top area of the usual Vindhyan type. The later are frequently aluminous. Raindrop, pitting as well as ripple marking has been observed in these Shales.

REFERENCE [A] Special Publication GSI Vol 28,83

[B] Fundamentals of Historical Geology and Stratigraphy of India, by Ravindra Kumar

3.2.2 Local geology:

The principal geological formations in the area are sand stone belonging to upper Vindhyan super group. Sand stone quartizitic in nature, which made harder to sand stone. They are brown/black in colour.

Geological Plan & sections are prepared at suitable interval on scale of **1:1000** (Plate no. III)

THE TOPOGRAPHIC PLAN OF THE APPLIED AREA PREPARED ON SCALE WITH CONTOUR INTERVAL 1M DEPENDING UPON THE TOPOGRAPHY OF THE AREA SHOULD BE TAKEN AS BASE PLAN FOR PREPARATION OF GEOLOGICAL PLAN. THE DETAILS OF EXPLORATION ALREADY CARRIEDOUT INCLUDING EVIDENCES OF MINERAL EXISTENCE SHOULD BE SHOWN ON GEOLOGICAL PLAN.

The scale of surface and surface geological mapping is 1:1000 with contour interval of 1m (**Please refer plate no. III**).

This is new quarry lease Case.

GEOLOGICAL SECTION: Prepared on 1:1000 scales (please refer plate no. III)

3.2 BROADLY INDICATE THE YEAR WISE FUTURE PROGRAMME OF EXPLORATION TAKING IN TO CONSIDERATION THE FUTURE PROGRAMME PLANNED IN NEXT ONE YEARS

- (i) Considering the geological occurrence there is no need of exploration
- (ii) Updated transverse section: Please refer plate no. III

*Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)*

(iii) Updated assay plan: As in the applied area there is no different grade of minerals hence therefore grade plan is not given.

3.3 GEOLOGICAL RESERVES & GRADE

As the area falls in protected forest, hence exploration and field survey could not be done due to the restriction of forest department under forest Conservation Act. However, the extension of the rock body has been recorded by studying nala sections found in the area. The reserves/resource has been calculated under the Stratiform, form of regular habit.

3.4 STRUCTURAL FINDINGS

As per present finding following litho sequence has been established over the running Mine area: It is massive body.

Weathered sandstone with siliceous soil: 0.50M

Quartzitic sand stone (gitti) is fine grained, brown/black Color in massive Form of tabular habit.-30 Meter

3.6 Geological Axis: In Stratiform deposit.

The area of 2.800 Ha. is geologically proved for stone (for making gitti) and depth wise influence is taken as per given information that Quartzitic sand stone (for making gitti) is continued for more than 30 m depth. Keeping the mining UPL about 30 m depth is considered under G1 category

A] MINERAL ZONE VOLUME IN M³

Parameters considered

1. Area: 2.800 Ha.
2. Present thickness of mineralization:30 m
3. Present knowledge: not required
4. Grade: not required (size as per required for road construction)
5. Mineral rejects=05%

S. J.
Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)

P. K. Tiwari
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

G1 M³

AREA M ²	THICKNESS M	VOLUME M ³	DEPLETED VOLUME OF M ³ (approx)	LEFT VOLUME OF IN M ³
28000	30	840000	NIL	840000

B] RESERVES UNDER BLOCKED CATEGORY

Parameters considered Unminable portion of lease area due to Barrier zone

Average perimeter along lease boundary for loss in 7.5m (G1) = 205841m³

Average cross sectional area along slope loss in G-1 zone = 24977M³

Mineral blocked in approach road. About 680 M² area blocked due to approach road and this area also included in sanctioned area.

Area x Mineral thickness x recovery

680 x 30 x 95% = 19380 M³

*Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)*

Further there are no any other losses due to legal provisions or cut of grade problem of Strata hence not considered.

MINERAL BLOKED IN BARRIER ZONE M ³	MINERAL BLOCKED IN MAINTING THE SLOPE OF BENCHES-T
AVERAGE PERIMETER X 7.5M X MINERAL THICKNESS-M X RECOVERY (95%) 963 X 7.5 X 30 X 95% = 205841M ³	AVERAGE CROSS SECTIONAL AREA IN M ² X MEAN LENGTH-M X RECOVERY) 313 X 84 X 95% M ³ = 24977M ³
230818M ³	

C] TOTAL MINERAL IN BLOCKED CATEGORY = 230818 (Barrier zone and bench slope) + 19380 (Approach road) = 250198M³

*P.K.Ti.
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013*

D) RESERVES AVAILABLE FOR MINING



AREA M ²	THICKNESS M	VOLUME M ³	MINERAL APPROACH BLOCKED IN BENCHES AND BARRIER ZONE IN M ³	RECOVERABLE VOLUME OF MINERAL IN M ³ (95%)
28000	30	840000	250198	560312

At present 560312m³ volumes available for mining

E) LIFE OF MINE: Average production of 39900 M³ of stone considered from the mine.

Life of mine = Total Recoverable reserve/Average Annual Production

$$= 560312/39900$$

$$= 14.04 \text{ Year say 14 Year.}$$

The life of mine may be change depend upon the rate of production.

J.S.
Regional Head
State of Geology & Mining
Regional Office Rewa (M.P.)


P.K.T.
Mining Surveyor
RQP/DR/2013/30/2613

CHAPTER-4

MINING

4.1 PROPOSED METHOD OF MINING

Proposed mining activity will be carried out by the new open cast semi machenised method of mining using hand tools such as spades, chisel, hammer etc. stone formation will be loosened by regular drilling and this will be transported from pit bottom to surface by machine and from the loading point of view, stone is transported by truck/dumper to the Stone crusher.



During the ensuing years the Stone quarrying will be according to the proposed method of semi mechanized way the following machines are proposed to be deployed on hire basis:

4.2 DETAILS OF MACHINERY:-

Semi Mechanized opencast mining method has been proposed. During development, hydraulic excavators will be used while developing. Tipper trucks will be used for transporting stone and waste. Earth moving machine while developing, Chisel, hammer tasla, rods Sufficient quantity will be used during mining operation. These machine will be used on hire basis as below-

S.No.	Particular	No.
01	Excavator	02
02	Rock Breaker	02
03	Drill Machine	01
04	Hyva	05
05	Water Tanker	01
06	Tractor	01

Signature
Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

4.3 YEARWISE PROPSED METHOD OF MINING

It will be commenced after the agreement and bhu pravesh with EC term and condition and the mining method will be the same as proposed with one production benches of 6.0m height while thin layer of OB will be scrapped ahead of working in sand stone formation and this thin layer of

OB is considered under waste and this waste is saleable or it will be used for making and maintenance of approach road.

YEARWISE PRODUCTION FOR THE FIRST FIVE YEAR

Year	Location	Average RL in (M)	No. of Bench	Area Excavated in (M ²)	Bench Height (M)	Total Vol. of Mineral in M ³	Volume in M ³ (95%)
1 st Year	AS SHOWN ON PLAN	331-325	1st	7000	6	42000	39900
TOTAL							39900
2 nd Year	AS SHOWN ON PLAN	331-326	1st	7000	6	42000	39900
TOTAL							39900
3 rd Year	AS SHOWN ON PLAN	331-326	1st	5977	6	35862	34069
		325-319	1Ind	1023	6	6138	5831
TOTAL							39900
4 th Year	AS SHOWN ON PLAN	325-319	1Ind	7000	6	42000	39900
TOTAL							39900
5 th Year	AS SHOWN ON PLAN	325-319	1IInd	7000	6	42000	39900
TOTAL							39900
GRANT TOTAL							199500 M3

Note: Production is taken from massive formation and after loosening the formation it is subjected to swelling factor by 10-25%.

4.4 YEAR WISE TOTAL PRODUCTION

YEAR	PRODUCTION M ³
FIRST YEAR	39900
SECOND YEAR	39900
THIRD YEAR	39900
FORTH YEAR	39900
FIFTH YEAR	39900
TOTAL	199500 M3


Regional Head
of Geology & Mining
Regional Office Rewa (M.P.)

Note: Production are taken from massive formation and after loosening the formation it is subjected to swelling factor by 10-25%.

4.5 PROPOSED RATE OF PRODUCTION WHEN THE MINE IS FULLY DEVELOPED

The average production will be 39900M³ (per year) or 159.6 M³ per day were working day calculated 250 days in a year

YEARWISE PRODUCTION FOR SECOND FIVE YEAR:-

YEAR	PRODUCTION M ³
FIRST YEAR	39900
SECOND YEAR	39900
THIRD YEAR	39900
FORTH YEAR	39900
FIFTH YEAR	39900
TOTAL	199500 M³

4.7 CONCEPTUAL MINING PLAN FOR ENTIRE LEASE PERIOD/CONCEPTUAL PERIOD BASED ON THE GEOLOGICAL MINING AND ENVIRONMENTAL CONSIDERATIONS

i) CONCEPTUAL EXPLORATION

Conceptual exploration not proposed.

ii) CONCEPTUAL LIFE OF QUARRY LEASE

The Life of Mine will about 9.04 say 9 years after this plan period because of deposit were left about 360812 M³.

iii) CONCEPTUAL TOP SOIL DUMP MANAGEMENT

There is negligible amount of top soil within the applied area. It will use for as road material. Other soil be used for afforestation.

iv) CONCEPTUAL RECLAMATION AND REHABILITATION:

In the conceptual period area will be developed up to 291MRL
Present reclamation and rehabilitation is not required.

a) About 1.998 Ha. area will be "mined out" at the end of five year.

- b) No area will come under reclamation and rehabilitation by the end of proposal period,
- c) Total mined area about 1.998 Ha at the end of five year period up to 319 MRL.
- d) About 1.998 Ha. Area will be rehabilitated by water reservoir.
- e) The mined out area will be wire fenced with gate and proper haulage road will be provided.

4.8 BACK FILLING: No Backfilling proposed for this plan period and conceptual period as per FCA 1980.

4.9 DEPTH OF MINING PROPOSED DURING PLAN PERIOD

During plan period 12 meters depth is proposed. After the depth of 6 meter from surface, lessee will take permission from DGMS and inform to govt. authority as per rules.

4.10 LAYOUT OF MINE WORKINGS FOR FACES AND SITES FOR DISPOSAL OF OVERBURDEN/ WASTE

During the five year period area within UPL ,will be developed and proposed benches will be developed as per shown in five year plan, bench height will be average 6 m each and the during the period pit bottom RL will reach from 331 MRL to 319 MRL . The proposal is given for systematic development with proper bench height. There is no overburden anticipated during the quarrying operation. The excavated weathered stone will be directly loaded into tipper to the needy crusher/other buyers for road project and construction works for filling leveling of low lying areas. It will be also used for maintenance of approach road for mine site and village road.

4.11 STRIPPING RATIO:- In surface mining, stripping ratio or strip ratio refers to the amount of waste or overburden that must be removed to release a given ore quantity. It is a number or ratio that expresses how much waste is mined per unit of ore. The units of a stripping ratio can vary

between mine types. This is case of stone and there is only weathered stone (quartzitic sandstone) in very negligible quantity which may be salable so stripping ratio not considered here.

4.12 ULTIMATE PIT LIMIT : In this quarry lease about 2.800 ha area is mineralized. Considering the ~~current~~ data and geology, pit layout is designed. The mining will be carried out in this plan period and in the conceptual stage up to 30 meter.

4.13 BLASTING: This granted area is a quarry Lease of sand stone blasting is required, therefore lessee will take all necessary permission and do accordingly DGMS norms.

4.14 DRILLING: Drilling of the blast holes is proposed by the compressed air operated jack hammer or Wagon Drill, height of the bench is proposed to be kept 6m. The specification of jack hammer or Wagon drill is as follow

a) DRILL PATTERN OF JACK HAMMER IS AS FOLLOW

Type	Make	No.	Dia Of Hole	Drilling Rod	Capacity	HP
Tractor compressor, or Jack Hammer	Atlas Copco	01	32mm	1500mm	110CFM	50

b) Specification of jack hammer is unit:

Type	Power	No.	Dia Of Hole	Drilling Rod	Capacity	HP
Jack compressor, Portable Compressor	Pneumatic Diesel	02 01	32 to 40mm	800x40 1500x34mm 300CFM	210CFM	50

4.15 TYPE OF EXPLOSIVE TO BE USED/ TO BE USED: Slurry explosive frequency of blasting will be once or two in a week. Delay detonators will be used.

4.16 STORAGE OF EXPLOSIVE: The applicant will engage an authorized

explosive agency to carry out the small amount of blasting and it will be supervised by competent and statutory foreman/ mines manager. The storage of explosive not proposed, Blasting should be done by only Govt. authorized agency after permission taken by authority.

4.17 PRECAUTION TO BE TAKEN DURING THE DRILLING AND

BLASTING: sufficient warning by signal is given in the entire area falling with danger zone, wet drilling will be used for blasting hole, control blasting will be done. Lessee will take all necessary permission and do accordingly DGMS norms. First Aid Box will be keeping ready at all the time. Necessary precautionary announcement will be carried out before the blasting operation.

4.18 TRANSPORTATION :- 05 trucks/Hywa of 10 m³ capacity are quite sufficient for transportation of mined out Stone (gitti).

Regional Head
Director of Geology & Mineral
Regional Office, Rewa (M.P.)

4.19 GREEN BELT - The green belt will be developed in lease area (barrier zone) and other places depending on availability of land by planting local species fruit plants.

P.K. Tiwari
Pushpendra Kumar Tiwari
ROP/DGMMP/30/2013

CHAPTER- 5

5.0 MINE DRAINAGE

a) LIKELY DEPTH OF WATER TABLE BASED ON OBSERVATION FROM NEAR BY WELL AND WATER BODIES.

The groundwater resource is available in the form of Hand pump/ dug well near the applied area and as per given information presently ground water table 50-60m BGL and the proposal are given quite above to GWT but in rainy season accumulated water has to be dewatered. Further the applied area is in vicinity of naturally water logged area and one pond in eastern direction. The average water retention during the rainy season is 2-6M and these water logged area has been protected by bund.

b) WORKING EXPECTED TO BE ABOVE/REACH BELOW WATER TABLE BY WHICH YEAR:

Ensuing five year period proposals are given up to 319 MRL which is about 30m above the ground water table. Further the proposals are given only for 12 m depth hence there will be no impact to adjacent and nearby water logged areas.

c) QUANTITY AND QUALITY OF WATER LIKELY TO BE ENCOUNTERED, PUMPING ARRANGEMENTS AND PLACES WHERE MINE WATER IS FINALLY PROPOSED TO BE DISCHARGED

During the rainy season rain water and seepage water will accumulate in the working work and this accumulated water will be discharged with the help of a 5 H.P. pump having capacity to lift 22,000 lit/hour with maximum head of 12-15 m. The pumped out water will be drained to the agriculture land on in Nallah as per the situation.

P.K.Ti
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

CHAPTER - 6

STACKING OF MINERAL REJECT AND DISPOSAL OF WASTE

a) RATE OF YEARLY GENERATION OF WASTE AND PROPOSALS FOR DISPOSAL OF WASTE NEXT FIVE YEAR:

This is New Case there is no any waste dumps within the applied area. The waste will be meager. The voids will be around 5% in Quartzites zone. Most of the OB and waste will be utilized for maintenance of approach road to mine site. During the five year plantation will be done in northeastern part (barrier zone) of the lease area. During the first five year separate lavatory for male and female will be constructed in east barrier zone area. Advance of benches will not be less then height of benches.

b) YEAR WISE GENERATION

YEAR	LATERITIC SOIL IN M3	OB WASTE IN M3	INTERCALATED WASTE IN M3
1 st Year	NIL	3500	NIL
2 nd Year	NIL	3500	NIL
3 rd Year	NIL	2989	NIL
4 th Year	NIL	NIL	NIL
5 th Year	NIL	NIL	NIL
TOTAL WASTE	NIL	9989 M3	NIL

c) LAND CHOOSEN FOR DISPOSAL OF WASTE WITH PROPOSED JUSTIFICATION

Not applicable

d) MANNER OF DISPOSAL OF AND CONFIGURATION, SEQUENCE OF BUILD OF DUMPS ALONG WITH THE PROPOSAL FOR THE STACKING OF SUB GRADE MINERAL, TO BE INDICATED YEARWISE

The excavated weathered stone will be directly loaded into tipper to the needy crusher/other buyers for road project and construction works for filling leveling of low lying areas. It will be also used for maintenance of approach road for mine site and village road.

e) PRECAUTION FOR CONFINEMENT OF DUMPS TO PREVENT POLLUTION OF SURFACE WATER BODIES / COURSES

Not applicable

F.
Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

CHAPTER -7

7.0 PROVISION FOR SEPARATE STACKING OF SURFACE SOIL EXCAVATED FROM MINING OPERATION AND ITS UTILITY

This is quarry lease case for stone quarry, keeping the negligible OB consideration OB/lateritic soil is likely to be generated.

a) LAND CHOOSEN FOR DISPOSAL OF WASTE WITH PROPOSED JUSTIFICATION

The waste dump of stone proposed to preparation of approach road to mine site.

b) MANNER OF DISPOSAL OF AND CONFIGURATION, SEQUENCE OF BUILD OF DUMPS ALONG WITH THE PROPOSALFOR THE STACKING OF SUB GRADE MINERAL, TO BE INDICATED YEARWISE

c) YEAR WISE GENERATION

*Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)*

YEAR	LATERITIC SOIL	OB WASTE	Mineral WASTE	LOCATION FOR DISPOSAL OF WASTE
1 st Year	NIL	3500	2100	used for maintenance of approach road for mine site
2 nd Year	NIL	3500	2100	
3 rd Year	NIL	2989	2100	
4 th Year	NIL	NIL	2100	
5 th Year	NIL	NIL	2100	
TOTAL WASTE	NIL	9989 M3	10500 M3	

d) LAND CHOOSEN FOR DISPOSAL OF WASTE WITH PROPOSED JUSTIFICATION

It will be used for maintenance of approach road for mine site.

e) MANNER OF DISPOSAL OF AND CONFIGURATION, SEQUENCE OF BUILD OF DUMPS ALONG WITH THE PROPOSALFOR THE STACKING OF SUB GRADE MINERAL, TO BE INDICATED YEARWISE

The overburden consists of Lateritic soil which is soft and friable and can

easily be removed JCB excavator. It is 0.3 to 0.7 meter in thickness (avg.0.5 meter). During the proposed five year mining lateritic soil will be generated which will be utilized for afforestation.

f) PRECAUTION FOR CONFINEMENT OF DUMPS TO PREVENT POLLUTION OF SURFACE WATER BODIES /COURSES

The overburden and mine waste will be loaded in to the tippers and unloaded mechanically by tippers. Mostly overburden and waste will be utilized for maintenance of approach road to mine site. The reject stone in form of lumps will be utilised as building material. There is no toxic constituent in lateritic soil and weathered intercalated so no adverse effect on surface water body. Surface water free from any toxic substances

g) PRECAUTION FOR CONFINEMENT OF DUMPS TO PREVENT POLLUTION OF SURFACE WATER BODIES /COURSES

The surface water in the form of seasonal rainfalls is the only source of water in the area. There is no manufacturing unit or beneficiation plant in the area so far and hence no surface water quality will be disturbed in this area.

S. J.
Regional Head
D'rade of Geology & Mining
Regional Office, Rewa (M.P.)

P.K. Tiwari

CHAPTER -8

USE OF MINERAL

8.1 CHANGES PROPOSED IN THE USE OF MINERALS, IF ANY

Lessee acquired this lease as to have captive quarry for the plant. Mineral will be used for road material and cement aggregate.

8.2 CHANGE IN THE SPECIFICATION, IF ANY, IMPOSED BY THE USER INDUSTRIES AND/ OR SPECIFICATION REQUIRED IN CASE OF NEW USER INDUSTRIES, IF ANY TO BE GIVEN.

No changes in specifications are imposed by user industry.

Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)


Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

CHAPTER -9

OTHERES

(a) SITE SERVICES

Site services for staff/Labours.

Mines Office With First Aid Facility	Tool Room	Shelter Room for Male	Shelter Room for Female	Lavoratory	
				Male	Female
28M ²	18M ²	21M ²	21M ²	6 M ²	6 M ²

(b) EMPLOYMENT POTENTIAL

1	Skilled	Supervisory staff	1
		Permit Manager/First Aid In charge	1
		Operator/ Mechanic	2
		Mines Manager/Mat	1
2	Semiskilled	Driver	2
		Mali/watchman/pump operator	1
3	Unskilled	Labour	8

(c) WELFARE MEASURES

First Aid Facility	First aid kits are kept in Mines office room, in case of such eventualities the victim will be given first aid immediately at the site and injured person will be taken to the hospital. Hospital is available at distance of 20Km (NE) in Hanumana the competent and Statutory foreman/ permit manager will be in charge of first aid.
Labour Health	As per Mines Rule, Periodic medical examination related to occupational health safety will be conducted to all the workers in applicants own cost.
Precautionary safety measures to the Laborers	Safety provisions like helmet, goggles, safety shoes, Dust mask, Ear muffs etc have to be provided as per the circulars and amendments made for Mine labours under the guidance of DGMS being a semi mechanized operation.

CHAPTER -10

MINERAL PROCESSING/BENEFICIATION

Mineral processing of ROM Mineral that is dressing, sizing & sorting etc. will be done at mine site or at crusher.

Regional Head
State of Geology & Mining
Regional Office (Rewa) (M.P.)

P.K.T.
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

CHAPTER - 11

11.0 ANY OTHER MATTER WHICH IS DIRECTED TO INCLUDE IN MINING PLAN

To comply the required particulars of Rules Regulation of MMR 1996 as per amendment made in Gazette notification dated 23rd March 2013.

11.1 RESULTS OF ANY INVESTIGATION CARRIED OUT FOR SCIENTIFIC MINING CONSERVATION OF MINERALS AND PROTECTION OF ENVIRONMENT, FUTURE PROPOSAL IF ANY.

- 1) The operation in the area yet to started and the mine production has not reached to its rated capacity so no such investigation is done so far.
- 2) For protection of dust while blasting and loading trucks, the care will be taken by spraying water on roads and working pits


Regional Head
D'vate of Geology & Mining
Regional Office, Rewa (M.P.)


Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

CHAPTER -12
ENVIRONMENT MANAGEMENT PLAN

12.1 BASE LINE INFORMATION

The base line information provides the data for prediction and evaluation of impacts of mining on biophysical and socio - economic environment .Relevant information for base line study and assessments are –

A	Type of land/ Khasra No	Govt. forest land/ 677/2 ka
B	Latitude	24°35'8.360"N to 24°35'15.607"N
C	Longitude	82° 0'23.678"E to 82° 0'34.858"E
D	Toposheet No.	63L/2
E	Village	Sardaman
F	Post Office	Sardaman
G	Tehsil	Hanumana
H	District	Rewa
I	State	Madhya Pradesh
J	Police Station	Hanumana
K	Hospital	Hanumana
L	School	Sardaman
M	Rest house	Hanumana
N	Airport	Jabalpur
O	Electricity	Sardaman
P	Bazar Place	Sardaman
Q	Total area applied for Quarry lease	2.800 Ha.
R	General Topography	Undulated
S	Human settlement	Nil
T	Dam/pond/lake	Nil
U	Forest	QL area is Forest land
V	National park / Monuments	Nil
W	National Highway/state Highway	Nil


Regional Head
D'Rate of Geology & Mining
Regional Office, Rewa (M.P.)

12.2 LAND USE PATTERN:

The total land under quarry lease is around 2.800 Ha which a part of Govt forest land Forest Comp. No. P-399 (Beat Sardaman, Range Hanumana, Rewa Division) Open Mixed Jungle. Presently the area comes under forest land for which the applicant will be applying for diversion of land under FCA 1980.

12.2.1 Landscape and Land Subsidence:

Topographically the area has part of undulating topography and as per information G1 has taken 20m thickness or up to and in ensuing one year and conceptual period average 6 M thick area will be developed by one bench of 6 M height

12.3 CLIMATIC CONDITION:-

The area proposed/under for quarry lease is characterized by sub tropical climate. The day temperature during summer rises as high as 46° C, but winter area generally pleasant with minimum temperature going down to 4° C in chilly winter days. The annual rainfall is 1000 mm average rainy days vary from 60 to 80 days during monsoon period.

12.4 WATER REGIME

From opening of quarry lease to conceptual period the proposal is given above GWT hence there will be no impact on GWT. The area is free from any water course the surface water in the area is mainly naturally precipitated water, which flows over the area for very short span of time during rains only. Ground Water condition in the nearby area seems to be good as observed in the adjoining village.

12.5 FLORA AND FAUNA -

Regionally the area falls under subtropical climatic zone and sustaining dry tropical land. The land under quarry lease is a protected forest land. The local neem, palas, tendu and babul and sagoun are common plants in the QL area. Species of common birds like crow, sparrow, and pigeon are rarely seen.

*Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)*

12.6 HUMAN SETTLEMENT

There is no human settlement in the proposed area. There is only one villages namely, Sardaman falls near 1 km from the area.

12.7 PUBLIC BUILDING, WORSHIP PLACES AND MONUMENTS

There are no such objectionable features in the area.

12.8 QUALITY OF AIR AND WATER

At present the area is free from any industrial pollution i.e. there is no source of water as well as air pollution in the area. The area forms a good ground water condition. Water from all sources is portable and is free from any hazardous elements.

12.8.1 AMBIENT AIR QUALITY: The area does not have any industrial activity in the core/ buffer zone and hence the ambient air quality good for habitants.

12.8.2 AMBIENT NOISE LEVEL: The area does not have any industrial activity in the core/ buffer zone and hence the ambient noise quality good for habitants.

12.8.3 AMBIENT WATER QUALITY: Quality of water is potable .The Groundwater of this area is free from pollution and is suitable for drinking purpose.

12.9 ENVIRONMENTAL IMPACT ASSESSMENT STATEMENT

1. Relevant information for evaluation of Impact of mining on environment:-

A) HEALTH AND HYGIENE: - in general the health of villagers is moderately good.

B) OCCUPATION :- Main occupation of the villagers is agriculture. Also works as Laborers in farms.

C) EDUCATION :- Mostly educated up to primary standard.

D) ECONOMIC CONDITION :- In general poor , due to lack of other avenues to earn other than agriculture.

12.10 INFORMATION ON ENVIRONMENT FEATURE

a) LAND ENVIRONMENT

i) LANDSCAPE :- The area falls in forest land. There is no major stream or drainage. Also no big escarpments & major geomorphic features. However local vegetation is found grown up in the area.

ii) AESTHETIC ENVIRONMENT :- Nothing special about aesthetic

S
Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

environment in the area.

iv) SOIL AND LAND USE PATTERN Forest Comp. No. P-399 (Beat Sardaman, Range Hanumana, Rewa Division) Open Mixed Jungle.

v) AGRICULTURE :- At present the land is not used for agriculture purpose.

FOREST :- The area under quarry lease is Forest land and forest clearance will be obtained from MoEF &CC. The conditions imposed by the MoEF &CC and the same will be implemented during the span of mining plan period.

vi) VEGETATION :- There is no important flora and fauna in existence. At present the area under question possess very few plants that too of bushes and not any big trees.

b) WATER ENVIRONMENT

SURFACE WATER :- No surface water bodies are available in the area.

i) **GROUND WATER :-** the area having elevated surface and water levels in the area are deeper side and bore wells are the major source of ground water in the area. The Mining operations will be above from water table hence no adverse impact is envisaged.

ii) **WATER QUALITY :-** the water from bore wells and dug wells is hygienic and unpolluted and no adverse effect has been noticed by the villagers in the past. There would be no change in the quality of ground water due to proposed mining activities

c) AIR ENVIRONMENT Mining activities are so planed, that there is no possibility of

- i) Pollution of air and ground water.
- ii) Adverse effect of human settlement.

NOISE :- The mining operation will be carried out semi mechanized at remote place hence there is no scope of noise pollution except momentary increase in noise level during drilling and blasting.

Signature
Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)

AIR :-The transportation vehicle, drilling and blasting operation will generate some dust for very short period, this will increase the spm level in the air, the spm level will not be more than permissible limit in any case. Sprinkler will be used in haulage road for minimizing dust.

d) SOCIO-ECONOMIC ENVIRONMENT :-

1. SOCIO-ECONOMIC BENEFITS ARISING OUT OF MINING.

There will be positive effect to some extent on socio-economic environment of the area as mining activity will assure job continuity of already engaged people also it may cause further job opportunities for additional people, which ultimately will improve the financial status of the local people.

2) SOCIAL & DEMOGRAPHIC PROFILE :- Main occupation of the villagers is agriculture. Also work as a laborers in farms. Mostly educated upto primary standard. Economic condition in general is poor due to lack of other avenues to earn other than agriculture.

3) OCCUPATIONAL HEALTH & SAFETY :- In general the health of villages is moderately good. The proposed mining activities are too small and semi mechanized. There would not be any pollution to noise, air and water. Moreover chemically no toxic substance is present in the deposit.

4) HUMAN SETTLEMENT:- The laborers will be engaged from the nearby village and as such there is no problem to human settlement. It is evident from the above information that the mining operation will not disturb the present environment and the life style of the people. Moreover the mining will help towards development of the area by solving unemployment problem to a certain extent.

5) RECREATION FACILITY :- At present there is only local festivals and visit to weekly market place are only source of recreation to the villagers. Mining activities will help to development of the area and by passage of time recreation facilities would also be increased.

7.
Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)



12.11 AFFORESTATION PROGRAMME :- About 500 Plants are proposed in Mining Plan Period. The area of plantation is marked and shown on plate of EMP. Plantation of wide leaf trees, tall grasses around the quarry pits, on OB dumps and also around the offices, are proposed.

Year	No. Saplings	Survival Rate	No. of Trees <i>APPROVED</i>	Expnd./ year	Location
I Year	100	80%	80	50000	Barrier Zone
II Year	100	80%	80	50000	
III Year	100	80%	80	50000	
IV Year	100	80%	80	50000	
V Year	100	80%	80	50000	
Total	500	80%	400	250000	

1. Base for selection of proposed plant species:

Selection of plant species is a **vital component for eco-restoration success**. The choice of plant species depends on the characteristics of soil, climatic conditions and ultimate land use. Grasses are more tolerant to adverse soil pH and moisture stress than legumes, and are, therefore, easier to establish. Pasture grasses and legume can be used for stabilization of spoil dumps. Trees and shrubs will be used where a wind break is desired or where visual shield is required and are also suitable to steep or rocky terrain and coarse waste.

Tree species *Boswellia serrata*, *Diospyros melanoxylon*, *Madhuca latifolia*, *Lagerstroemia parviflora*, *Buchanania lanza*, *Anogeissus latifolia*, *Lannea coromandelica*, *Semecarpus anacardium*, *Cassia fistula*, *Emblica officinalis*, *Terminalia tomentosa* and *Holarrhena antidysentrica* are already found in the area of Central India forests. It means that edaphic as well as climatic conditions are suitable for the growth of these species. *Azadirachta indica*

and *Cassia siamea* are fast growing species and have wider adoptability towards edaphic and climatic conditions.

Being the mega tree *Ficus* species are proposed for plantation. The grass species mentioned are early soil binders and bushes fast growing.

The availability of moisture in the soil, especially during warm dry summer, is important. If water level is not high enough, irrigation will be needed to provide moisture. As the vegetation matures, the need for the irrigation diminishes, since, grasses get adapted to dry summer conditions.

The species selected for establishment will also depend on the future land use of the area, soil conditions and climate.

List of plant species recommended for plantation

S.No.	Local Name	Botanical Name
1	Karanja	<i>Pongamia Pinnata</i>
2	Neem	<i>Azadirachta indica</i>
3	Amaltas	<i>Cassia Fistula</i>
4	Mahua	<i>Madhuca indica</i>
5	Bahera	<i>Terminalia belerica</i>
6	Ficus	<i>Ficus Benjamin</i>

S. T.
Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

Mango Neem, Karanj, Subabool, and Golmohar. Sapling will be planted in 30-cm. deep hole covered with soil and manure. Mali will take care of plants for better survival conditions.

12.12 LAND USE PATTERN The present land use pattern in the lease area (prior to commencement of mining operations) comprised of Forest land. The details of the land use at various stages of the mining operations are given in

P.K. Tiwari
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

Table-

Sr. No.	Details	Existing Land Use	After 5 Years	After 10 Years	At The End of Mine Life
1	Area excavated		1.998	1.998	1.998
2	Storage for topsoil		-*	-*	-*
3	Storage for OB		-*	-*	-*
4	Infrastructure		0.01	0.01	-
5	Roads/Approach road		0.140	0.140	0.060
6	Greenbelt over safety zone		0.652	0.652	0.742
7	Plantation of forest Dept.	2.800 Ha	-	-	-
TOTAL		2.800 Ha	2.800 Ha	2.800 Ha	2.800 Ha.

Note: *: The OB of QL is proposed to preparation of approach road to mine site and little amount of soil generated and it will be used for plantation purpose.



Regional Head
 Directorate of Geology & Mining
 Regional Office, Rewa (M.P.)


 Pushpendra Kumar Tiwari
 RQP/DGMMP/30/2013

CHAPTER-13

PROGRESSIVE MINE CLOSURE PLAN

13.01.1 BRIEF INTRODUCTION OF THE AREA

i	Name of Applicant	Swami Nityanandji Maharaj Stones
ii	Address	Prop. Shri Lalit Panghal, R/o House no. 975/76, Sector 13, Hudda, Bhiwani, District Bhiwani, Haryana
iii	Phone	8307520901
iv	Status of Applicant	Proprietorship Firm
v	Mineral(s), which occurring in the area and which the applicant intends to mine	Sand stone (quartzitic nature) 
vi	Proposed Quarry Lease Period	10 Year (from agreement)
vii	Plan Period	5 Year
viii	Category of Mine	B

13.01.2 DETAILS OF THE AREA:

i	District	Rewa
ii	Taluka	Hanumana
iii	Village	Sardaman
iv	Area	2.800 Ha.
v	Khasra No.	677/2 ka
vi	Occupancy	Govt. Forest Land


Regional Head
 Directorate of Geology & Mining
 Regional Office, Rewa (MP)

a) Whether area is recorded in forest: Yes

b) Existence of public road: No public Road is passing through the lease area.

c) Toposheet No.: Area falls in survey of India Toposheet No.63 L/2

d) CO-ORDINATE OF CORNER POINT OF QUARRY LEASE

Corner Point	Latitude	Longitude
A	24°35'8.360"N	82° 0'23.678"E
B	24°35'13.003"N	82° 0'27.096"E
C	24°35'15.340"N	N82° 0'32.540"E
D	24°35'15.807"N	82° 0'34.858"E
E	24°35'10.911"N	82° 0'30.039"E
F	24°35'6.519"N	82° 0'24.950"E

Source: DGPS survey report

e) Land use pattern: Govt. forest land.

f) Validity of lease period: The period for the lease will be 10 years from the date of execution as per MPMMR rule 1996.

13.01.02 METHOD OF MINING AND MINERAL PROCESSING:

Open cast semi mechanized mining methods.

13.01.03 REASON FOR CLOSURE

As per Rule Minor Mineral Rules and latest amendment vide Gazzette notification dated 23RD March 2013 and progressive mine closure plan has been opted because of mining operation are yet to be started and suppose to be continued till the existence of the mineral in the area.

13.01.04 STATUTORY OBLIGATIONS

The area under quarry lease is Forest land and forest clearance will be obtained from MoEF &CC. The conditions imposed by the MoEF &CC and the same will be implemented during the span of mining plan period.

No statutory obligations are there; routine legislative conditions were mentioned in the approval letter .The details as required

Any special condition while execution of lease: No

Any imposed conditioned by MoEF or Central Pollution Board: It will be as per Mo EF/MPPCB/CPCB rules. Directorate of Mines and Safety.


Regional Head
 Directorate of Geology & Mining
 Regional Office, Rewa (M.P.)

13.01.04 CLOSURE PLAN PREPARATION

i	Name of Applicant	Swami Nityanandji Maharaj Stones
ii	Address	Prop. Shri Lalit Panghal, R/o House no. 975/76, Sector 13, Hudda, Bhiwani, District Bhiwani, Haryana
iii	Phone	8307520901

MINE DESCRIPTION

13.02.01. TOPOGRAPHY

Please refer page no. 5

13.02.02 REGIONAL GEOLOGY

Please refer page no. 5-8

13.02.03 LOCAL GEOLOGY

Please refer page no. 8

13.02.04 RESERVES AND RESOURCE

Please refer page no. 9-11

13.02.05 UP DATED RESERVES

Updated reserves will be the same as geological reserves.


Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

13.02.06 MINING METHOD

Please refer page no. 12

13.02.07 MINERAL BENEFICIATION: -

Please refer page no. 20

13.03 REVIEW OF IMPLEMENTATION OF MINING PLAN OF MINING INCLUDING ONE YEARS PROGRESSIVE CLOSURE PLAN UP TO THE FINAL CLOSURE OF MINE

Not applicable as it is a new Case.

13.04 CLOSURE PLAN

13.04.01 MINED OUT LAND

About 1.998 Ha. Area mined out at the end of plan period

13.04.2 WATER QUALITY MANAGEMENT:

There are no surface water bodies; the ground water is available in the

form of dug well near the applied area. Ground water level is below the conceptual pit depth proposed as per the present knowledge of deposit. After the completion of mining operations in this area the surface water is likely to be contaminated due to wash off from the dust prone area. The same be controlled by adequate plantation before the conceptual period is over.

During present PMCP period to conceptual period following steps will be taken for water quality management:

1. There is no surface water body, the water table is quite below the proposed one year and conceptual working, hence there will be no impact on ground water
2. Proposal of settling tank: During the rainy or post Monsoon season the collected water within the pit will be passing through the settling tanks to settle the suspended heavy particles the clear water will be discharged to agriculture land /nallah
3. The garland drain will be provided around the dump, whatever wash off from higher altitude area then it will be further drain to settling tank to suspend if any heavy particles then it will drain to agriculture field or nallah

The Stone does not contain any toxic element which is likely to cause surface/ground water pollution. Mining operation will not pose any problem to general water table of area.

13.04.03 AIR QUALITY MANAGEMENT: -

Once the mining operation in this area is over the ambient air can only be polluted by dust raised from the waste dumps. As stated above the waste dumps will be stabilized and secured against dust being air borne by adequate plantation before the conceptual period is over.

At the end of conceptual period following steps will be taken for air quality management:

1. Adequate plantation.
2. If required then regular sprinkling of water over the dust zone.

Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)

The proposed mining operation are small, hence there will be no such impact on air quality management.

13.04.04 WASTE MANAGEMENT

NO dumps are present after five year

13.04.05 TOP SOIL MANGEMENT:

Top soil generate for the one year and conceptual period and it used for road construction.

13.04.06 TAILING DAM MANAGEMENT:

No tailing generation hence tailing dam management is not required.

13.04.07 INFRASTRUCTURE

During the plan period mine office, separate toilet for men and women and shelter room will be constructed and first aid facilities will be enhanced.

(i) Any decommissioning proposal: No

13.04.08 DISPOSAL OF MINING MACHINERY

As such there is no mining machinery.

13.04.09 SAFETY AND SECURITY

For mining activity separate watch man will be appointed for security of mine. First aid facility will be provided at mine site. Fencing will be provided around the working pit, which will restrict the fall of animal in to working pit. Entrance of general public will be restricted and can be permitted if necessary with prior permission of manager/ supervisor/lessee.

13.04.10 DISASTER MANAGEMENT: -

High-risk accidents are not anticipated in the area because proposed mining is of small scale. In case of natural disaster such as earthquake, flood, storm etc., as per the situation, lessee will take the assistance from the local competent authority of govt. and non-govt. agency, similarly mines manager will be in touch of local people for immediate amelioration and in the case of flood in the local nallah which is between 1-2 km (aerial) in radial direction will take anticipatory care in coordination with state govt. directives. Further the proper maintenance and replacement of

required machineries of crusher unit will be taken care to avoid the any accidental event.

13.04.11 CARE AND MAINTENANCE DURING TEMPORARY DISCONTINUANCE

Special precautions and guidelines will be followed giving by the Central/State government for unplanned mining operations. Proposed mining is of small scale mine, most of the mining facilities will be adopted on hire basis in such case care will be taken as per the terms and conditions of the contract. During the temporary discontinuous of mining operations, Chokidar will be appointed for protection of mine site.

13.5 ECONOMIC REPERCUSSION OF CLOSURE OF MINE AND MANPOWER RETRENCHMENTS

Proposed mining is of small scale mine, most of the mining facilities will be adopted on hire basis in such case care will be taken as per the terms and conditions of the contract. So far the crusher unit which is on contractual basis will be dealt as per their terms and condition of contract. At the conceptual stage the crushing unit will be shifted and reinstalled in applicant private where the engaged workers will be shifted as per their contractual term and condition.

10.5.1 NUMBER OF LOCAL RESIDENTS EMPLOYED IN THE MINE, STATUS OF THE CONTINUATION FAMILY OCCUPATION AND SCOPE OF JOINING THE OCCUPATION:

The number of local resident are propose to employ will be around 05-06 from the nearby areas and these local people have already their own traditional and family occupations like agriculture, sundry jobs and having their huts and in future when mine totally closed down due to exhaustion of reserves or other reason, they can easily join to their respective employments.

10.5.2 COMPENSATING GIVEN OR TO BE GIVEN TO THE EMPLOYEES CONNECTING WITH SUSTENANCE OF HIMSELF AND THEIR FAMILY MEMBERS:

S
Regional Head
State of Geology & Mining
Regional Office, Rewa (M.P.)

For employees the retrenchment compensations to the workers, as and when required will be done as per the Central Labour Legislations.

10.5.3 SATELLITE OCCUPATION CONNECTED TO THE MINING INDUSTRY-NUMBER OF PERSON ENGAGED THEREIN -CONTINUANCE OF SUCH BUSINESS AFTER MINE CLOSE:

This is New Case and there is no proposal for closing of mining operation during the plan period or up to lease period. There are other mines also operation in the vicinity of the area. The workers mostly works in seasonal agriculture and hence satellite occupations connected to the mining industry are not considered. Hence, after the mines closes there will not be any adverse effect.

10.5.4 CONTINUED ENGAGEMENT OF EMPLOYEES IN THE REHABILITATED STATUS OF MINING LEASE AREA AND ANY OTHER REMNANT ACTIVITIES:

This is very little chance of quarry Lease area getting rehabilitated as the land is Govt. Land.

10.5.5 Envisaged repercussions on the expectation of the society around due to closure of mine:

The employment potential of the mines is small; hence it will have no repercussion on the society around due to closure of mine. While the employment potential remain the same

10.6 TIME SCHEDULING FOR PROGRESSIVE RECLAMATION AND REHABILITATION.

The details of time schedule of all abandonment operations as lease in Para 4 should be described here. The manpower and other resources required for completion of lease job should be described. The schedule such operation should also supplementary by PERT (Programme Evaluation and Review Technique) Bar chart etc.:

It is not applicable at this stage because the mining operations are yet to be started and will be continuing for forthcoming period. There will not be any mined out area or generation of soil dump during the proposal period

hence no reclamation and rehabilitation is envisaged. As discussed in foregoing chapters there is no proposal for abandonment of mine or initiating closure operations during the mining plan period so at this station no question of abandonment does not arise.

13.07 COSTS FOR PROGRESSIVE RECLAMATION AND REHABILITATION

The applicant has applied for grant of mining lease and mining operation will commence after the grant of mining lease therefore at this stage it is not possible to assess the abandonment cost. However for first one year the abandonment cost for implementation the protective and measures including their maintenance and monitoring programmed will be about Rs.100000.00, which is discussed as below:

(i) Progressive reclamation and rehabilitation measure:

Not applicable.

(ii) Plantation:

About 500 plants are proposed during plan period the cost for maintaining the plantation is as follows:

Cost: Rs.10000.00 & Care and maintenance: Rs 245000.00

(iii) Parapet:

Not proposed.

(iv) Bund/Garland:

Not proposed

(v) Retaining/Toe wall:

Not proposed

(vi) Settling Tank:

Not proposed

(vii) Miscellaneous: It will be around Rs.100000.00


Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)


Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

Proposal	Cost in Rs.
Reclamation/Rehabilitation	0000.00
Plantation	250,000.00
Parapet	-
Bund/Garland	-
Toe wall	-
Settling Tank	-
Miscellaneous	100000.00
Total	350000.00



13.08 FINANCIAL ASSURANCE


Regional Head
 Director of Geology & Mining
 Regional Office, Rewa (M.P.)

Total area is 2.800 Ha. hence as per Rule 42(5) in sub clause (a) of clause (6) of sub rule (j) of MPMMR 1996 financial assurance calculation will be 75000.00 per ha. 2.800 HaX75000 (Per Ha.)=Rs.225000.00

This FA will be submitted after the necessary instruction from approval officer and it will be submitted before the final submission.

13.09 CERTIFICATE: Refer annexure no. IV


 Pushpendra Kumar Tiwari

RQP/DGMMP/30/2013

PUSHPENDRA KUMAR TIWARI

PLACE: REWA

DATE: 12/12/2021

RQP/DGMMP/ 30/2013

CONSENT FROM THE APPLICANT

I hereby accept all content given in this Mining Plan by the recognized person may be deemed to have been made with my knowledge and consent and shall be acceptable to me and binding on me in all respect, "understood the contents of the Mining Plan and agree to implement".

Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)


Applicant
Lalit Panghal

(For M/s Swami Nityanandji Maharaj Stones)

P.K. Tiwari
Pushpendra Kumar Tiwari
RQP/DGMMP/30/2013

UNDERTAKING

I, Lalit Panghal, Proprietor of Swami Nityanandji Maharaj Stones R/o House no. 975/76, Sector 13, Hudda, Bhiwani, District Bhiwani, Haryana, Proprietor of Sardaman Stone Quarry lease, Tehsil Hanumana, District Rewa (M.P.) hereby undertake that



1. We will obtain all consent approval from competent authorities like SPCB, MoEF & CC. We also commit that environmental degradation like air, water, noise and vibration will be kept within permissible limits.
2. Water sprinkler for dust suppression during the transportation of material will be done within the lease area.
3. We also commit that the unnecessary cutting of trees will be avoided.

Place: Rewa

(Lalit Panghal)

Date: 12 / 12/2021

Proprietor


Regional Head
Division of Geology & Mining
Regional Office, Rewa (M.P.)



संचालनालय भौमिकी तथा खनिकर्म मध्यप्रदेश

मध्यप्रदेश गौण खनिज नियम 1996 के अंतर्गत
मान्यता प्राप्त योग्य व्यक्ति

प्रमाण पत्र



श्री पुष्पेन्द्र कुमार तिवारी, पिता श्री राम किशोर तिवारी, पता ग्राम एवं पोस्ट लोही, तहसील हुजूर, जिला रीवा, मध्यप्रदेश, जिनकी फोटो तथा हस्ताक्षर अभिप्राणित है, को म.प्र. गौण खनिज नियम 1996 के अंतर्गत मान्यता प्राप्त योग्य व्यक्ति के रूप में प्रदत्त पंजीयन क्रमांक RQP/DGMMP/30/2013, दिनांक 10.05.2018 से 09.05.2023 की अवधि के लिये नवीनीकृत किया जाता है।

मान्यता प्राप्त व्यक्ति के हस्ताक्षर - P. V. T. -

भोपाल, दिनांक 10.05.2018


संचालक
भौमिकी तथा खनिकर्म
मध्यप्रदेश, भोपाल

कार्यालय कलेक्टर (खनिज शाखा) जिला—रीवा (म.प्र.)

E-mail- modgmrew@mp.gov.in

क्रमांक/ ८५३९

/खनिज/ 2021

रीवा दिनांक....11.12.2021

प्रति,

स्वामी नित्यानंद जी महाराज रसोन्हा,
प्रो. श्री ललित पधाल
निवारी मकान नंबर ९७५/७६ रोड १३,
हुड्डा भियानी, हरियाणा

विषय :- ग्राम सरदमन तहसील हनुमना जिला रीवा के खसरा नं. ६७७/२क पी. (वन भूमि) रकवा ०३.४०० हेठो क्षेत्र पर खनिज यांत्रिक किया से गिट्टी बनाने हेतु पत्थर (अर्थात् क्रेशर के उपयोग हेतु) का उत्खनिपट्टा आवेदन पत्र क्रमांक ७८१ दिनांक १८.१२.२०२० के निराकरण विषयक।

संदर्भ :-

- कार्यालयीन पत्र क्रमांक ४४४ / खनिज/ 2021 रीवा, दिनांक ११.०१.२०२१
- आपका पत्र दिनांक ०७.०७.२०२१

---X---X---X---

उपरोक्त विषयान्तर्गत आपके द्वारा ग्राम सरदमन तहसील हनुमना जिला रीवा के खसरा नं. ६७७/२क पी. (वन भूमि) रकवा ०३.४०० हेठो क्षेत्र पर खनिज यांत्रिक किया से गिट्टी बनाने हेतु पत्थर (अर्थात् क्रेशर के उपयोग हेतु) उत्खनिपट्टा आवेदन पत्र १० वर्ष की अवधि के लिये दिनांक ११.१२.२०२० को इस कार्यालय में प्रस्तुत किया गया था।

वन भण्डलाधिकारी रीवा के प्रतिवेदन अनुसार आवेदित क्षेत्र वन भूमि है जो कि खसरा नं. ६७७/२क पी. (वन भूमि) के अंतर्गत है। प्रकरण में आवश्यक परीक्षण उपरांत प्राप्त प्रतिवेदनों के आधार पर रीवा जिले के ग्राम सरदमन तहसील हनुमना खसरा नं. ६७७/२क पी. (वन भूमि) रकवा ०३.४०० हेठो में से उपलब्ध रकवा ०२.८०० हेठो क्षेत्र पर खनिज यांत्रिक किया से गिट्टी बनाने हेतु पत्थर (अर्थात् क्रेशर के उपयोग हेतु) उत्खनिपट्टा १० वर्ष की अवधि के लिये स्वीकृत करने का निर्णय लिया जाकर सैद्धान्तिक सहमति संदर्भित पत्र दिनांक ११.०१.२०२१ द्वारा प्रदान की गई थी। कोविड संक्रमण के कारण समयावधि में कार्यवाही पूर्ण नहीं होने के दृष्टिगत रखते हुये म.प्र. गौण खनिज नियम १९९६ के नियम १८ (२) में निहित प्रावधानों के अनुरूप पूर्व सैद्धान्तिक स्वीकृति में अवधि वृद्धि की जाती है।

आप इस सैद्धान्तिक सहमति पत्र जारी होने के दिनांक से ०६ माह के अंदर अनुमोदित खनन योजना इस कार्यालय में उपलब्ध करायें। अनुमोदित खनन योजना एवं वन संरक्षण अधिनियम १९८० के अंतर्गत यन विभाग के अनुमति प्राप्त कर इस कार्यालय में उपलब्ध कराने के पश्चात् ही उत्खनिपट्टा स्वीकृत आदेश जारी किये जा सकेंगे।

(कलेक्टर महो० द्वारा अनुमोदित)


प्रभारी अधिकारी-खनिज
हेतु कलेक्टर जिला रीवा (म.प्र.)

ग्राम पंचायत क्षेत्र सरदमन, जनपद पंचायत हनुमना, जिला रीवा म0प्र0
मांक/क्षू-1

सरदमन, दिनांक/02/01/2021

अनापत्ति प्रमाण - पत्र

प्रमाणित किया जाता है कि ग्राम पंचायत क्षेत्र सरदमन अंतर्गत शासकीय भूमि खसरा नंवर 677/2/क, रकवा 3.400 हेक्टेयर में यांत्रिकी विधि से पत्थर उत्खनन कर गिट्टी निर्माण हेतु आवेदित भूमि खसरा नंवर 677/2/क, राजस्व भूमि के स्थान पर कक्ष क्रमांक पी.एफ. 399 बीट हरई प्रताप सिंह की वनभूमि है। उक्त भूमि में आवेदक/संस्थान द्वारा वनभूमि को खोदकर खदान के रूप में बदलने के संबंध में वन संरक्षण अधिनियम 1980 का यदि उलंघन नहीं किया जाता तो ग्राम पंचायत को कोई आपत्ति नहीं होगी। जिसका अनापत्ति प्रमाण—पत्र ग्राम पंचायत द्वारा प्रदाय किया जाता है।


सर
ग्राम पंचायत क्षेत्र सरदमन
जनपद पंचायत हनुमना
जिला रीवा म0प्र0

कार्यवृत्त पुस्तक

ફિલેબ વાર્ષિક એસ્યુ

समिलन की तारीख 01/01/2021 समिलन का रथान 10:00 बजे समिलन का समय 10:00 बजे विषय सदस्यों की संख्या 156
परिवर्तन 10:00 बजे समिलन का रथान 09:45 बजे

प्रा के समय स्वर्ग गये विषय	समिलन का कार्यवृत्त
1	2

<p>इतामा निर्माण की समर्थन करता हो तो विनियोग के अनापनि अमां पत्र जारी रखता होगा। वैकल्पिक उपचार यह एसलेटोफ्रेडियाल एसलेटोफ्रेडियाल हारा करता होगा जि�स अवधि तक उन निरीक्षक ने दूसरा नियम नहीं ओवर रखता राजस्व द्वारा नहीं होता है। वन शाम वन्श नमूना P-377 के अंत मध्य 60.6.87. कानून अधिकार अधिकार अवधि अवधि आता है।</p>
<p>वैकल्पिक उपचार असलेटोफ्रेडियाल नियम, जिसका द्वारा वन शाम ने अपेक्षक अधिकार द्वारा दिया गया 1980 का उल्लंघन की नियम खाता हो जाए तो असलेटोफ्रेडियाल अनापनि अमां पत्र प्रदान कर्त्तव्य आपको नहीं देती जाया आगे उल्लंघन के अनापनि अमां पत्र प्रदान किया जाता है। इनपर को सभी समाजिक सेवा विभाग और अधिकार अधिकार द्वारा अधिकार द्वारा दिया जाता है।</p> <p style="text-align: right;">संसद संसद संसद संसद</p> <p>परिवेश संरक्षण विभाग परिवेश संरक्षण परिवेश संरक्षण</p>

नपरी + परा


३१५ - लरमन ९५८

५८ - लरमन ९५

३१८ - अपराह्न

३१९ - छुमना

३११ - दीवाली ()



देव - अन्नपूर्णा देव - अन्नपूर्णा देव - अन्नपूर्णा

पूर्णा देव - २०२१ ।

पूर्णा देव - २०२१ ।



१८/१२ - २०२०
५८ अक्टूबर २०२०



132

119

Digitally signed by DS C J MAMONIER LAND RECORDS AND SETTLEMENT MADHYA PRADESH 1
Date: 2020-12-17 11:58:52 IST
Reason: Digital Extract of Land Record - Khajra Copy
CLER No.: 11130655000000000034

लय तहसीलदार तहसील-हनुमना जिला-रीवा (म0प्र0)

४३।/प्रवा०/२०२०

हनुमना, दिनांक 26.12.2020

कलेक्टर महोदय
(खनिज शाखा)
जिला-रीवा (म0प्र0)

पथः— ग्राम सरदमन की आराजी क्रमांक 677/2/क रकवा 03.400 हे० उत्खनि क्षेत्र में पर्यावरणीय सम्मति हेतु सिया द्वारा निर्धारित बिंदु का जांच प्रतिवेदन।

दर्भा:— कार्यालय कलेक्टर (खनिज शाखा) जिला रीवा का पत्र क्रमांक 5404/खनिज/2020 रीवा दिनांक 18/12/2020।

—००—

विषयान्तर्गत ग्राम सरदमन की आराजी क्रमांक 677/2/क रकवा 03.400 हे० में उत्खनि क्षेत्र में पर्यावरणीय सम्मति हेतु सिया द्वारा निर्धारित बिंदु पर जांच राजस्व निरीक्षक पिपराही/हल्का पटवारी सरदमन से कराई गई। राजस्व निरीक्षक पिपराही/हल्का पटवारी सरदमन द्वारा मौके से जांच की जाकर पर्यावरणीय सम्मति हेतु सिया द्वारा निर्धारित बिंदु का प्रतिवेदन प्रस्तुत किया गया है।

प्रकरण में संलग्न राजस्व निरीक्षक/हल्का पटवारी रिपोर्ट से यह स्पष्ट है कि प्रस्तावित भू-खण्ड के 10 किमी० की परिधि में कोई नेशनल पार्क व अभ्यारण्य नहीं तथा मानव बसाहट नहीं है। प्रस्तावित भू-खण्ड में शैक्षणिक संस्थान, विकित्सालय, पुरातत्व धरोहर तथा राष्ट्रीय महत्व के स्मारक व नदी तालाब नहीं हैं तथा प्रस्तावित भू-खण्ड बन भूमि है।


अतः पर्यावरणीय सम्मति हेतु सिया द्वारा निर्धारित बिंदु का जांच प्रतिवेदन सहपत्रों सहित सादर सम्प्रेषित है।


संलग्न:— उपरोक्तानुसार।

तहसीलदार
तहसील-हनुमना
जिला-रीवा (म0प्र0)

पर्यावरणीय सम्मति हेतु सिया द्वारा निर्धारित बिन्दु

प्र०	निर्धारित बिन्दु	वरतुरिति
1.	वहा 10 विंग्गी की दूरी में कोई नेशनल पार्क/ पार्कराण्ड/ जैवविविधता स्थित है? तो उसकी दूरी	नहीं है।
2.	खनिपट्टा/ उत्कर्षनिपट्टा/ घोम निकाय खदान से या उन छेत्र की दूरी कितनी है?	वहा 250 मी. दूरी की दूरी है।
3.	वहा 500 मीटर की दूरी के अंदर कोई भागव बसाहट/ शैक्षणिक संस्थान/ चिकित्सालय/ पुरातत्त्व धरोड़र/ राष्ट्रीय महत्व के स्मारक स्थित है? तो उसकी दूरी	नहीं है।
4.	वहा 500 मीटर की दूरी के अंदर कोई जलीय निकाय/ नदी/ तालाब/ नहर स्थित है? तो उसकी दूरी	नहीं है।
5.	500 मीटर की परिधि में खींचूरा अथा खनिपट्टा/ लीज की जानकारी (रेत के प्रकरण में यह जानकारी 1000 मीटर रहेगी)	50 मी. की दूरी पर लेखक उत्तम विकासी की जलीय नहर बनायी जाएगी।
6.	रेत उत्खनन के प्रकरण में नदी का नाम	—


 20/12/2020
 20/12/2020
 20/12/2020


 20/12/2020
 20/12/2020
 20/12/2020

कार्यालय वनमण्डलाधिकारी, वनमण्डल सा० रीवा (म.प्र.)

जयन्ती कुंज, डिरिया, रीवा

E-Mail- dfot.rwa@mp.gov.in , Phone- 07662- 251335

क्रमांक / भा.चि. / ०५

रीवा, दिनांक ०१.१२.२०२०

प्रति,

कलेक्टर (खनिज शाखा)
जिला रीवा (म.प्र.)

विषय :- ग्राम सरदमन तहसील हनुमना के खसरा नम्बर ६७७/२/क रक्वा ३.४०० हे. भूमि पर अनुज्ञाप्ति / उत्खनन पट्टा पत्थर यांत्रिकीय विधि से गिट्टी निर्माण हेतु आवेदक रवामी नित्यानंद जी महाराज स्टोन्स प्रो. ललित पंधाल।

संदर्भ :- आपका पत्र क्र. / ५३९५ / खनिज / २०२० रीवा, दिनांक १८.१२.२०२०

—०—

विषयान्तर्गत संदर्भित पत्र से प्राप्त प्रकरण का मौका निरीक्षण उप वनमण्डलाधिकारी मऊगंज एवं वन परिक्षेत्राधिकारी हनुमना के द्वारा की गई, जिसमें उप वनमण्डलाधिकारी मऊगंज एवं वन परिक्षेत्राधिकारी हनुमना के प्रतिवेदन अनुसार उक्त भूमि वन भूमि है।

उक्त प्रकरण भारत सरकार पर्यावरण एवं वन मंत्रालय जलवायु परिवर्तन मंत्रालय भोपाल की स्वीकृति / अधिरोपित शर्तों तथा वन संरक्षण अधिनियम १९८० के पालन हेतु प्रकरण की सैद्धांतिक स्वीकृति आदेश, माइनिंग प्लान अनुमोदित होने का सकाम अधिकारी का पत्र की कौपी इस कार्यालय को उपलब्ध करावें, जिससे वन संरक्षण अधिनियम १९८० के तहत व्यपवर्तन की कार्यवाही की जा सके।

अतः प्रतिवेदन आपकी ओर आवश्यक कार्यवाही हेतु प्रेषित है।

(चन्द्रशेखर सिंह भावजे.)

वनमण्डलाधिकारी

वनमण्डल(सा.)रीवा(म.प्र.)

पृष्ठांकन क्रमांक / भा.चि. / ०६

रीवा, दिनांक २०२०

प्रतिलिपि :-

० (-०१ -२)

1. उप वनमण्डलाधिकारी मऊगंज की ओर सूचनार्थ प्रेषित।

2. वन परिक्षेत्राधिकारी हनुमना की ओर सूचनार्थ प्रेषित।

(१) वनमण्डलाधिकारी
वनमण्डल(सा.)रीवा(म.प्र.)

कार्यालय क्षेत्रीय प्रभुख
खनिज साधन विभाग, मध्यप्रदेश शासन
संचालनालय भौमिकी तथा खनिकर्म
क्षेत्रीय कार्यालय रीवा मध्यप्रदेश
ई मेल - rhdgmrew@mp.gov.in

फोन एवं फैक्स नं. 07662 222044, 222045

क्रमांक ०७ /भौ./न.क्र./2020-21

रीवा दिनांक 02/01/2021

इति

प्रभारी अधिकारी खनिज
जिलाध्यक्ष कार्यालय
ज़िला रीवा (म.प्र.)

विषय - शाम सरदमन 968 तहसील हनुमना जिला रीवा के खसण नवर 677/2/क रक्का 03.400 है, में खनिज पत्थर (यांत्रिकीय विधि से गिर्हनिर्माण) का उत्खनिपट्टा हेतु आवेदन पत्र। आवेदक स्वामी गित्यानंद जी महाराज स्टोर्स प्रो. ललित पंधाल।
राजदूत - आपका पत्र क्रमांक 5400/खनिज/2020 रीवा दिनांक 18.12.2020

—00—

उपरोक्त क्षेत्र का निरीक्षण किया गया। आवेदित क्षेत्र के अक्षांश देशांश के जानकारी के अन्वय में आवेदक द्वारा बताए गए आवेदित क्षेत्र एवं आत्मपास रियल क्षेत्र एवं इस छद्मनों में विद्यमान चट्टानों के संस्तर का अवलोकन किया गया। क्षेत्रीय भौगोलिक एवं जूरामंच रियल के अनुसार क्षेत्र में विन्ध्य समूह की चट्टानें विद्यमान हैं। क्षेत्र में पाया जान वाला खनिज एंड स्टोन है, जो फर्टिजिटिक प्रकृति का है, जिसे गोप खनिज के लाए बैठाता है। खनिज एंड स्टोन है, जो फर्टिजिटिक प्रकृति का है, जिसे गोप खनिज के लाए बैठाता है। क्षेत्र में अन्य किसी प्रकार का भिन्नरत्नांशेशन नहीं देखा गया है। जैसे जामका 1,70,000 घन मीटर खनिज उपलब्ध हो सकता है।

क्षेत्रीय प्रभुख

संचालनालय भौमिकी तथा खनिकर्म


क्षेत्रीय कार्यालय रीवा मध्यप्रदेश

1/5397/एवं/2020

खनि निरीक्षक का प्रतिवेदन
उत्थनिपटा/पूर्वोक्त अनुज्ञाप्ति/खनिपटा
कार्यालय द्वारा भरा जाए

B.M. 18.12.2020

- आवेदक का नाम— रमामी नित्यानंद जी महाराज स्टोर्स, प्रो. ललित पंधाल।
- आवेदित क्षेत्र
 - आ ग्राम — सरदमन १५८
 - व तहसील — हनुमना
 - स जिला— रीवा
 - द रक्षा— ०३.४०० हेठ
 - इ खसरा कमांक— ६७७/२/क
- आवेदन का प्रकार — उत्थनिपटा
- आवेदित खनिज— यांत्रिकीय विधि से गिट्टी निर्माण
- आवेदन प्रस्तुत का दिनांक— १७.१२.२०२०
- प्रतिवेदन प्रस्तुती हेतु अवधि—
(अधिकतम १५ दिवस)


(हस्ताक्षर)

खनि शाखा प्रभारी/उपसंचालक/
खनि अधिकारी/सहायक खनिअधिकारी

(खनि निरीक्षक द्वारा भरा जाए)

- रथल निरीक्षण का दिनांक —
- खनि नियमों के अनुसार आवेदित क्षेत्र से प्रतिवंशित दूरी

(1) पुल	लौह
(2) राष्ट्रीय/राजमार्ग	लौह
(3) रेल्वे लाइन	लौह
(4) नदी/नाला/नहर	लौह
(5) जलाशय/यांत्र	लौह
(6) ग्रामीण भार्ग	पक्की
(7) सार्वजनिक संस्थान	लौह
(8) आवासी	लौह
(9) सार्वजनिक उपयोग की भूमि	लौह
(10) धार्मिक रथल	लौह
(11) भरघट	लौह
- आवेदित खनिज की प्रारंभिक उपलब्धता
संबंधी प्रतिवेदन
- आवेदित क्षेत्र के आसपास अन्य रथीकृत
खनि रियायतों का विवरण—
क्रमांक ग्राम खसरा खनिज खनि रियायत
- आवेदित क्षेत्र नवीन है, अथवा पूर्व में क्षेत्र में खनन हुआ है।
- अन्य कार्य आवश्यक जानकारी
- आवेदित क्षेत्र के संबंध में
रथीकृत/अरथीकृत संबंधी स्पष्ट अनुशंसा
दिनांक २-१-२१

हस्ताक्षर
(खनि निरीक्षक का नाम)

मानचित्रकार का प्रतिवेदन

1.	आवेदक का नाम	गित्यानन्द जी महराज रटोन प्रो. ललित पैद्याल			
2.	आवेदित क्षेत्र	सरदमन			
	(अ) ग्राम	हनुमना			
	(ब) तहसील	शीवा			
	(स) जिला	3,400 रु०			
	(द) रकवा	677/2क अंश भाग			
	(इ) खसरा क्रमांक				
3.	आवेदन का प्रकार	उत्थानिपट्टा			
4.	आवेदित खनिज	पत्थर (यांत्रिकी क्रिया से गिट्टी निर्माण)			
5.	आवेदन प्रस्तुति का दिनांक	18/12/2020			
6.	वया आवेदित क्षेत्र सुरक्षित है अथवा नहीं?	नहीं			
7.	आवेदित क्षेत्र पूर्व में धारित है अथवा नहीं?	नहीं			
8.	आवेदित क्षेत्र यदि पूर्व में धारित था तो उसका पूर्ण विवरण (पट्टेदार का नाम, श्वीकृत अवधि, खनिज का नाम एवं क्षेत्र निरस्त होने का कारण) खनि रियायत अवधि समाप्ति के पश्चात् खुला घोषित हुआ अथवा नहीं	नहीं			
9.	यदि क्षेत्र खुला घोषित है तब खुला घोषित होने की अधिसूचना अनुसार आवेदित क्षेत्र के मानचित्र की स्थिति एवं रकवा	नहीं			
10.	आवेदित क्षेत्र पर पूर्व के आवेदन लिखित है अथवा नहीं? (लिखित होने पर विस्तृत विवरण)	नहीं			
11.	आवेदित क्षेत्र पूर्व के आवेदनों से आच्छादित होता है तब क्षेत्र उपलब्धता क्षेत्र का विवरण	हो			
12.	प्रतिबंधित क्षेत्र छाड़ने के उपरान्त स्पलब्ध क्षेत्र (निर्धारित प्रारूप में प्ररतुत करें)				

आवेदित क्षेत्र		प्रतिबंधित क्षेत्र		श्वीकृति हेतु उपलब्ध / प्रस्तावित क्षेत्र	
खसरा क्र.	रकवा	खसरा क्र.	रकवा	खसरा क्र.	रकवा
677/2क पी.	3,400 रु०	677/2क पी.	0.600 रु०	677/2क पी.	2,800 रु०



13.	आवेदित क्षेत्र का इतिहास	<p>— आवेदित क्षेत्र शासकीय वन भूमि है। समरत स्थलीय प्रतिवेदन तहसीलदार, ग्राम पंचायत, क्षेत्रीय प्रमुख, खनि निरीक्षक द्वारा प्राप्त प्रतिवेदन अनुसार आवेदित भूमि का संपूर्ण भाग वन भूमि है। आवेदित क्षेत्र ऊबड़-खाबड़ व पथरीली पड़त भूमि है।</p> <p>वन मण्डलाधिकारी वन मण्डल रीवा द्वारा प्राप्त प्रतिवेदन अनुसार आवेदित क्षेत्र वन भूमि है, भारत सरकार पर्यावरण वन एवं जलवायु परिवर्तन मंत्रालय क्षेत्रीय कार्यालय भोपाल की अधिरोपित शर्तों तथा वन संरक्षण अधिनियम 1980 के तहत आवेदित क्षेत्र व्यपवर्तन की कार्यवाही किये जाने हेतु वन विभाग को कोई आपत्ति नहीं बताई गई है।</p> <p>वन मण्डलाधिकारी के प्रतिवेदन के आधार पर संपूर्ण आवेदित क्षेत्र सैद्धांतिक सहमति की स्थीकृत हेतु शासन निर्देशों के अनुलेप उपलब्ध गान्य किया जा सकता है।</p>
14	क्षेत्र उपलब्धता संबंधी स्पष्ट अनुसंशा नवशे में भी अंकित की जाये	<p>— अतः उक्त क्षेत्र उपलब्धता संबंधी प्रतिवेदन अग्रेम कार्यवाही हेतु सादर प्रस्तुत है।</p>

दिनांक :— ०२.०१.२०२१


 (वीर सिंह)
 सहा, मानचित्रकार
 खनिज शाखा, जिला—रीवा (म.प्र.)

GOOGLE MAP



GOOGLE MAP


2015

00 20 40
00 200 400
RF - 1:4000

60 CM
600 M



Scale - 1:4000



INDEX

SL. No.	SYMBOL	DESCRIPTION
01		LEASE BOUNDARY
02		CONTOUR
03		TEMP. BENCH MARK
04		AGRICULTURAL LAND
05		WASTE LAND
06		BARREN LAND

LAND USE PLAN

THIS PLAN AND AREA - 2.80 Ha.
SECTION MADE UP VILLAGE - Saradhaman 958
BY BEST OF MY TEHSIL - Hanumana
KNOWLEDGE DISTRICT - Rewa (M.P.)
Khasra No.877/2ka

CLIENT

Swami Nityanandji Maharaj Stones
Prop : Shri Lalit Panghal
/o: H.No. 975/76, Sector 13, Hudda,
Bhiwani, Distt. - Bhiwani, Haryana

P.K.T.
Pushpendra Kumar Tiwari
H.O.D. G.M.P. 30/2013

N

W E S

LOCATION AND KEY MAP

MADHYA PRADESH

PRODUCED BY AN AUTODESK EDUCATIONAL PRODUCT



INDIA




PLATE :-

LOCATION AND KEY MAP

THIS PLAN & SECTION MADE UP BY BEST OF MY KNOWLEDGE	AREA - 2.80 Ha. VILLAGE - Saradhaman 958 TEHSIL - Hanumana DISTRICT - Rewa (M.P.) Khasra No.677/2ka
--	---

CLIENT

Swami Nityanandji Maharaj Stones
Prop : Shri Lalit Panghal
R/o: H.No. 975/76, Sector 13, Hudda,
Bhiwani, Distt.-Bhiwani, Haryana


NAME

P.V.T:-
Pushpendra Kumar Tiwari
PUSHPENDRA KUMAR TIWARI
RQP/DCGM/P/30/2013
RQP/DCGM MP/30/2013

REWA



Regional Head
Directorate of Geology & Mining
Regional Office, Rewa (M.P.)



INDEX

SL No.	SYMBOL	DESCRIPTION
01		LEASE BOUNDARY
02		ULTIMATE PIT LIMIT
03		CONTOUR /RL
04		TEMP. BENCH MARK
05		SPOT LEVEL
06		QUARRY LEASE
07		

SURFACE PLAN


THIS PLAN & AREA -2.80 Ha.
SECTION MADE VILLAGE- Saradhaman 958
UP BY BEST OF TEHSIL - Hanumaha
MY KNOWLEDGE DISTRICT - Rewa (M.P.)
Khasra No. 877/2ka

CLIENT

Swami Nityanandji Maharaj Stones
Prop : Shri Lalit Panghal
R/o: H.No. 975/76, Sector 13, Hudda,
Bhiwani, Distt. -Bhiwani, Haryana

Regional Head
D'rate of Geology & Mining
Regional Office, Rewa (M.P.)

A horizontal scale bar with numerical markings from 10 to 110 in increments of 10. The markings are black numbers on a white background. Below the scale bar, the text "Scale - 1:1000" is centered in a black font.



Regional Head
State of Geology & Mining
Regional Office, Rourkela (M.P.)

INDEX		
SL. No.	SYMBOL	DESCRIPTION
01		LEASE BOUNDARY
02		ULTIMATE PIT LIMIT
03		CONTOUR
04		TEMP. BENCH MARK
05		PROP. 5YEAR WORKING
06		PROP. 5YR. PLANTATION
07		SECTION LINE
08	331.0	PROP. RL
09		QUARRY LEASE




PROP. FIVE YEAR PLAN & SECTION
 THIS PLAN & AREA - 2.80 Ha.
 SECTION MADE VILLAGE - Saredhaman 958
 UP BY BEST OF TEHSIL - Hanumana
 MY KNOWLEDGE DISTRICT - Rewa (M.P.)
 Khasra No. 677/2ka


CLIENT
Swami Nityanandji Maharaj Stones
Prop : Shri Lalit Panghal
R/o: H.No. 975/76, Sector 13, Hudda,
Bhiwani Distt -Bhiwani, Haryana

NAME **Pushpendra Kumar Tiwari**
RQP-DGM MP/30/2013
PUSHPENDRA KUMAR TIWARI
RQP-DGM MP/30/2013

Pushpendra Kumar Tiwari
ROPDGMP/30/2013

BCB/BCMMB/30/3013







Regional Head
Directorate of Geology & Mining
Region Office, Rewa INDEX

SL No.	SYMBOL	DESCRIPTION
01		LEASE BOUNDARY
02		ULTIMATE PIT LIMIT
03		CONTOUR
04		TEMP. BENCH MARK
05		PMCP WORKING
06		PMCP PLANTATION
07		WATER BODY AREA

PROGRESSIVE MINE CLOSURE PLAN	
THIS PLAN & SECTION MADE UP BY BEST OF MY KNOWLEDGE	AREA - 2.80 Ha. VILLAGE - Saradhaman 958 TEHSIL - Hanumana DISTRICT - Rewa (M.P.) Khasra No. 677/2ka
CLIENT	Swami Nityanandji Maharaj Stones Prop : Shri Lalit Panghal R/o: H.No. 975/76, Sector 13, Hudda, Bhiwani, Distt.-Bhiwani, Haryana
NAME	PUSHPENDRA KUMAR TIWARI RQP/DGM MP/30/2013


P. K. T.
PUSHPENDRA KUMAR TIWARI
RQP/DGM MP/30/2013






Regional Head
State of Geology & Mining
Regional Office, Rewa (R.P.)

SL No.	SYMBOL	DESCRIPTION
01		LEASE BOUNDARY
02		ULTIMATE PIT LIMIT
03		CONTOUR
04		TEMP. BENCH MARK
05		PROP. WORKING SECTION
06		PROP. 5YR. PLANTATION
07	X1 / X2	SECTION LINE
08	⊕ 331.0	PROP. RL
09		QUARRY LEASE

PROP. SURFACE & GEOLOGICAL PLAN	
THIS PLAN & SECTION MADE P BY BEST OF MY KNOWLEDGE	
CLIENT	AREA - 2.80 Ha. VILLAGE- Saradhaman 958 TEHSIL -Hanumana DISTRICT -Rewa (M.P.) Khasra No.677/2ka
Swami Nityanandji Maharaj Stones Prop : Shri Lalit Panghal /o: H.No. 975/76, Sector 13, Hudda, Bhiwani, Distr.-Bhiwani, Haryana	
NAME	P.V. Tiwari PUSHPENDRA KUMAR TIWARI RQP/2013 ROP/DGJM MP/30/2013





Regional Head
State of Geology & Mineral
Regional Office, Rewa

SL No.	SYMBOL	DESCRIPTION
01		LEASE BOUNDARY
02		ULTIMATE PIT LIMIT
03		CONTOUR
04		TEMP. BENCH MARK
05		PROP. WORKING SECTION
06		PROP. 5YR. PLANTATION
07	X_1 / X_2	SECTION LINE
08		PROP. RL
09		QUARRY LEASE

CONCEPTUAL PLAN AND SECTION	
IS PLAN & CTION MADE Y BY BEST OF Y KNOWLEDGE	AREA - 2.80 Ha. VILLAGE - Saradhaman 958 TEHSIL - Hanumana DISTRICT - Rewa (M.P.) Khasra No.677/2ka

MENT

wami Nityanandji Maharaj Stones
rop : Shri Lalit Panghal
/o: H.No. 975/76, Sector 13, Hudda,
hiwani, Distt.-Bhiwani, Haryana

AME
Pushpendra Kumar Tiwari
PUSHPENDRA KUMAR TIWARI
B.R.D.M.C. B/30/2013
ROP/DGM/MP/30/2013