<u>Transportation of the minerals proposed to be raised from the mining lease:</u>

Blasted material will be loaded with hydraulic excavators of bucket capacity of 2.5 to 4.0 cum into 35/50 ton capacity dumpers and will be transported to proposed crushing & screening plant for production of lump& fines. Dumpers of 15/25T capacity would be utilized for shifting of crushed ore to the stack-yard. Marketable ore will be dispatched by road through trucks of different capacities and rail. Waste generated will be transported to proposed waste dump.

Front-end-loaders & hydraulic excavators of 2.5 to 3.5cum bucket capacity will be deployed for required re-handling works.