ROJECT REPORT FOR DEPARTMENTAL EXTRACTION AND TRANSPORTATION OF TIMBER IN ANTNAG FOREST DIVISION FOR THE YEAR 2020-21 OF CO. NO. 20b/k BLOCK LARNOO RANGE DAKSUM

No. Item	Description		
1 Location	Daksum		
2 Area of compartment	145 Hec.		
3 Nature of work	Extraction/Transportation of Timber		
4 Type of Marking	Trees coming under the alignment of construction of Tourist Facilitation centre and security cabin Daksum		
5 Marked Volume	######################################		
6 Expected Outturn	Expected Outturn 1015		

PARAMETRERS OF THE PROJECT

Extraction

1	Average rolling lead (chainage)	C	Chains		
2	Topography /Terrain	a) 50	b) 29	c) 21	d) 00
3	Chainage as per topography	a) 0	b) 0	c) 0	d) 0
4	Rates as per approved tariff	a) 1.06	b) 0.77	c) 0.55	d) 0.0.25
5	Financial implications involved on ac	count of rolling	g/dragging	upto KLP (R	s:/Cft/Chain)

	a) 0	b) 0	c) 0	d) 0	Total = 00
S. No	Particulars of Work	Unit	Rate (Rs/Unit)	Quantity Cfts	Amount (Rs.)
1	Felling of green standing trees	1015	2.86	1015	2902.9
2	Delimbing /Debarking conversion and Snouting.	1015	5.71	1015	5795.65
3	Rolling Dragging upto KLP over an average lead of 70 Chains	1015	0	1015	0
4	Loading at KLP	1015	5.15	1015	5227.25
5	Transportation from KLP to PLP over lead of 3 KM @ Rs 3.91/KM	1015	11.73	1015	11905.95
6	Unloading at PLP	1015	0.06	1015	60.9
7	Loading at PLP	1015	5.15	1015	5227.25
8	Total Extraction		30.66		31119.9
10	Transportation to various depots over an average lead of 40 km @ Rs 0.36/KM/CFT			3	
11	Un-loading at destination		1		
12	Enumeration Of trees Rs./tree	24	4	24	96
13	Marking of trees Rs./Tree	24	8	24	192
					288
	Grand Total Extraction	et .			31407/=

> Certified that all the precautionary measures have been taken for the safeguard of the regeneration.

> Certified that chainage shown in the rolling/dragging is based on the fact..

Prepared and submitted By

-

DFO Anantnag

I/C Block Officer Larnoo

Forest Division Anantnag

Attested By

Forerest Range Daksum Suit

The second second	7	Ver	tail of year wise bre	ak up of require	ment of funds is as under	The property
: No.	Year	No. of trees to be felled	No. of plants to be planted(10 times the No. of trees felled)	Maintenance	Rate/plant	Amount 11165.00
1	Oth Year	24	240	Nil		2791.00
2	1 "Year	24	240	(@)25%		1675.00
3	2 th Year	24	240	15%	<u> </u>	1117.00
4	3 th Year	24	240	10%	Planting per conifer poly	
5	4 th Year	24	240	10%	pot @ Rs 29.34	1117.00
6	5 th Year	24	240	10%	Plant production/Nur.cost	1117.00
7	6 th Year	24	240	10%	per poly pot @ Rs 17.18	1117.00
8	7 th Year	24	240	10%	TOTAL= Rs. 46.52	1117.00
9	8 th Year	24	240	10%]	1117.00
10	9 th Year	24	240	10%		1117.00
11	10 th Year		240	10%		1117.00
4.4	To real	2-4	Total			24567.00
	Supervision Charges Additional 17.5% Departmental charges			4299.00		
12				1228.00		
13	Additional 5% centergencies charges Grand Total				30094.00	

Prepared by

Counter signed

Attested

1/C B.O Larnoo Officer
Forest Block Lownoo

visional Forest Officer

Forest Division Anantnag

UNDERTAKING FOR PAYMENT OF NPV AND OTHER COMPONENTS

It is to certify that I, Chief Executive Officer Tourism Development Authority Kokernag, have applied for diversion of 04 kannals(0.2 hac) of forest area for the purpose of "Construction Of Tourist Facilitation Centre and Security Cabin at Daksum". I hereby ,undertake to pay the net present value(NPV) of the above forest land . I/We also hereby undertake to pay the additional amount of NPV, if so determined as per the decision of the Hon`ble Supreme court . I also undertake to pay the amount as assessed for the compensatory Afforestration, compensation of trees and other components as decided in the case.

Place: Rokernag.

Date 06/05/2020

Chief Executive Officer Tourism
Development Authority
Kokernag